


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	BRIDGE
				0004 URBAN	0011 084-6019
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	383	383	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1183	1183	
44000600	SIDEWALK REMOVAL	SQ FT	5390	5390	
• 50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	24	24	
50200100	STRUCTURE EXCAVATION	CU YD	115		115
• 50200300	COFFERDAM EXCAVATION	CU YD	306		306
• 50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	1		1
• 50201102	COFFERDAM (TYPE 1) (LOCATION - 2)	EACH	1		1
50300225	CONCRETE STRUCTURES	CU YD	481.7		481.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	294.3		294.3
50300260	BRIDGE DECK GROOVING	SQ YD	1188		1188
• 50300280	CONCRETE ENCASEMENT	CU YD	23.8	14	9.8
50300300	PROTECTIVE COAT	SQ YD	1633		1633

• SEE SPECIAL PROVISIONS

FILE NAME	USER NAME	DESIGNED	REVISIONS	 <b>Allen Henderson &amp; Associates, Inc.</b> Civil and Structural Engineers Springfield, IL 62703 Phone: (217)544-8033 IL Design Firm No. 184-001907	<b>SUMMARY OF QUANTITIES</b> SCALE: NONE SHEET NO. 3 OF 9 SHEETS STA. TO STA.		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILE#	#USER#	DRAWN	REVISIONS				8006	10-00470-00-BR	SANGAMON	90	5
PLOT SCALE = #SCALE#		CHECKED	REVISIONS				CONTRACT NO. 93600				
PLOT DATE = #DATE#		DATE	REVISIONS				FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				