



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 3, 2019

SUBJECT: Various Routes
Section 16-00112-14-PP
Sangamon County
Contract No. 93726
Item 135
June 14, 2019 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 2 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bid.

Very truly yours,

Jack A. Elston, P.E.
Bureau Chief
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with a small "P.E." to the right.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

GENERAL NOTES


- WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE ANY SUCH MONUMENTS ARE MOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL THE PROPERTY MARKS AND MONUMENTS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.
- THE THICKNESS OF HOT-MIX ASPHALT MIXTURES SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HOT-MIX ASPHALT WILL BE PLACED.
- MINOR AGGREGATE SHOULDER WORK MAY BE NECESSARY BEYOND STA. 179+11 AT THE EAST END OF SPAULDING ORCHARD ROAD TO TIE IN WITH THE ADJACENT CONSTRUCTION SECTION. THE 4' AGGREGATE SHOULDER WIDTH SHALL BE MAINTAINED TO THE TIE IN POINT AS DETERMINED BY THE ENGINEER. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF AGGREGATE WEDGE SHOULDERS, TYPE B. NO ADDITIONAL COMPENSATION WILL BE ALLOWED.


APPLICATION RATES UTILIZED IN QUANTITY CALCULATIONS


BITUMINOUS MATERIALS (IN-PLACE RECYCLING)....	1.6 GAL/SO YD
HOT-MIX ASPHALT	112 LBS/SO YD/INCH
BITUMINOUS MATERIALS (PRIME COAT).....	0.15 LBS/SO FT
BITUMINOUS MATERIALS (TACK COAT - MILLED)...	0.05 LBS/SO FT
BITUMINOUS MATERIALS (TACK COAT - LIFTS).....	0.025 LBS/SO FT
BITUMINOUS MATERIALS (COVER COAT).....	0.38 GAL/SY
BITUMINOUS MATERIALS (SEAL COAT).....	0.33 GAL/SY
COVER COAT AGGREGATE (5/8").....	23 LBS/SY
SEAL COAT AGGREGATE (3/8").....	28 LBS/SY

HOT-MIX ASPHALT MIXTURE REQUIREMENTS			
MIXTURE NUMBER:	NO. 1	NO. 2	NO. 3
MIXTURES - USES:	SURFACE COURSE	BINDER COURSE (1.75")	PATCHING/ANCHORMENTAL
AC/PG	PG 64-22	PG 64-22	PG 64-22
DESIGN AIR VOLTS:	4.0% - 4.0% Design = 50	4.0% - 4.0% Design = 50	4.0% - 4.0% Design = 50
MIXTURE COMPOSITION: (GRADATION MIXTURE)	IL-9.5	IL-9.5	IL-9.5
FRICTION AGGREGATE:	MIX "C"	N/A	N/A
QUALITY MANAGEMENT:	OC/QA	OC/QA	OC/QA

A 5/31/2019

APPROVED Feb 14 2019

 COUNTY ENGINEER

PASSED 3-6 2019

 DISTRICT SIX ENGINEER OF LOCAL ROADS & STREETS

Releasing For Bid Based on Limited Review 3-6 2019

 REG. FOUR ENGINEER

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SHEET 2 OF 32

GENERAL NOTES & SIGNATURES
 FAS 633 (CH31)
 FAU 8048 (CH23)
 SECTION 16-00112-14-PP
 SANGAMON COUNTY
 SANGAMON COUNTY
 HIGHWAY DEPARTMENT



K U H N & T R E L L O
 CONSULTING ENGINEERS
 A Limited Liability Company
 109 N. 7th Street, 3rd Floor
 Springfield, IL 62703
 Phone: 217-679-0044
 Professional Design Firm No. 184-006516

A ADDENDUM NUMBER