

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				ROADWAY 0006 RURAL
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	1540	1540
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1.1	1.1
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	1304	1304
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	224	224
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	580	580
44213000	PATCHING REINFORCEMENT	SQ YD	2108	2108
44213200	SAW CUTS	FOOT	7324	7324
44213204	TIE BARS 3/4"	EACH	8106	8106
45100100	CRACK ROUTING (PAVEMENT)	FOOT	210,727	210,727
45100200	CRACK FILLING	POUND	73757	73757
67100100	MOBILIZATION	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	18	18
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28	28



FILE NAME =	USER NAME = NOLASCOCJ	DESIGNED -	REVISED -
pw:\planroom dot.illinois.gov\PWIDOT\Documents\IDOT	offices\District 3\Projects\0366J85\CADData\0366J85-sht-details	DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/27/2019	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(50-8)PP	LASALLE	15	3
CONTRACT NO. 66J85			ILLINOIS FED. AID PROJECT	

CRACK ROUTING AND SEALING SCHEDULE				
LOCATION	LONGITUDINAL CRACK ROUTING (PAVEMENT)	TRANSVERSE CRACK ROUTING (PAVEMENT)	LONGITUDINAL CRACK FILLING	TRANSVERSE CRACK FILLING
MP TO MP	FOOT	FOOT	POUND	POUND
SOUTHBOUND				
70.0 TO 71.0	16350	43032	5723	15061
71.0 TO 72.0	16040	53616	5614	18766
72.0 TO 73.0	14036	35760	4913	12516
73.0 TO 74.0	16416	45517	5746	19429
74.0 TO 75.0	17343	36578	6070	12795
75.0 TO 76.0	16225	35080	5679	12558
76.0 TO 76.5	8290	27444	2902	9500
SUB-TOTAL	104700	287472	36647	100615
NORTHBOUND				
70.0 TO 71.0	16419	23400	5747	8190
71.0 TO 72.0	16545	28512	5791	9979
72.0 TO 73.0	16631	36096	5821	12634
73.0 TO 74.0	16006	32880	5602	11508
74.0 TO 75.0	16098	28416	5634	9946
75.0 TO 76.0	16288	37464	5701	13112
76.0 TO 76.5	8040	13536	2814	4738
SUB-TOTAL	106027	200304	37110	70106
TOTAL	210727	487776	73757	170721

PAVEMENT MARKING SCHEDULE					
LOCATION	LENGTH	POLYUREA PVMT MRK TYPE I		RAISED REFLECTIVE MARKER	RAISED REFLECTIVE MARKER REMOVAL
		LINE 4" WHITE	LINE 6" WHITE		
MP TO MP	FOOT	FOOT	FOOT	EACH	EACH
SOUTHBOUND					
70.0 TO 71.0	222	222	10	21	21
71.0 TO 72.0	100	100	10		
72.0 TO 73.0	54	54	10		
73.0 TO 74.0	186	186	13		
74.0 TO 75.0	77	77	10		
75.0 TO 76.0	44	44			
76.0 TO 76.5	75	75	10		
SUB-TOTAL		758	63	21	21
NORTHBOUND					
70.0 TO 71.0	135	135	10	20	20
71.0 TO 72.0	116	116	10		
72.0 TO 73.0	235	235	10		
73.0 TO 74.0	96	96	10		
74.0 TO 75.0	89	89	10		
75.0 TO 76.0	147	147	11		
76.0 TO 76.5	6	6			
SUB-TOTAL		824	61	20	20
TOTAL		1582	124	41	41