



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 5, 2019

SUBJECT: FAP Route 322 (US 51)
Project NHPP-X91E(540)
Section 3CR-1
Jackson County
Contract No. 78635
Item No. 200, June 14, 2019 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Table of Contents to the Special Provisions
2. Added page 40 to the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.
Bureau Chief
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger P.E.'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

CWR/cr

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
UTILITIES	1
TRAFFIC CONTROL PLAN	3
TWO WEEK NOTIFICATION PRIOR TO STARTING WORK	4
PORTABLE CHANGEABLE MESSAGE SIGNS	4
BOX CULVERT REMOVAL AND REPLACEMENT	5
ASSEMBLE AND MATCH MARK PRECAST CONCRETE BOX CULVERT	5
DROP-OFF NEAR THE EDGE OF TRAVELED WAY	5
TRAFFIC CONTROL AND PROTECTION STANDARD BLR 21	6
WEEP HOLE DRAINS FOR ABUTMENTS, WINGWALLS, RETAINING WALLS AND CULVERTS	6
MEMBRANE WATERPROOFING SYSTEM FOR BURIED STRUCTURES	6
COMPENSABLE DELAY COSTS (BDE)	8
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	12
DISPOSAL FEES (BDE)	21
EQUIPMENT PARKING AND STORAGE (BDE)	22
LIGHTS ON BARRICADES (BDE)	23
PAYMENTS TO SUBCONTRACTORS (BDE)	24
PORTLAND CEMENT CONCRETE (BDE)	24
PROGRESS PAYMENTS (BDE)	25
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	25
STEEL PLATE BEAM GUARDRAIL MANUFACTURING (BDE)	37
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	37
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	38
TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (BDE)	38
TRAFFIC CONTROL DEVICES - CONES (BDE)	39
WEEKLY DBE TRUCKING REPORTS (BDE)	39
WORKING DAYS (BDE)	39
SOIL BORING LOG	40

SOIL BORING LOG

ILLINOIS DEPARTMENT OF TRANSPORTATION
 District Nine Materials

Bridge Foundation
 Boring Log
 Sheet 1 of 1

AP 322 (US 51) Over creek
 Route: FAP 322 (US 51) Structure Number: 039-7061 Date: 4/4/2016
 Section: 1-4)Y; 3Y-1 Bored By: R Moberly
 County: Jackson Location: Milepost 20.3 Checked By: R Moberly

Boring No	DEPT	BLOWS	Qu	W%	Surf Wat Elev:	DEPT	BLOWS	Qu	W%
1-S					95.4				
Station 535+32					Ground Water Elevation				
Offset 6' LT CL					when Drilling 90.4				
Ground Surface 99.9 Ft					At Completion 80.5				
					At: Hrs:				
99.9 Ft is Approx 395.00 Ft									
Augered to 7.0 feet									
					Bottom of hole = 21.0 feet				
					Free water was observed at 9.5 feet				
	5.0				Elevation was referenced to CL US 51 at CL of box culvert; Assumed Elevation = 100.0 feet	30.0			
					Boring advanced using hollow stem augers (8" O.D., 3.25" I.D.)				
	92.9				To convert "N" values to "N60" multiply by 1.25				
Soft, very moist, grey, Silty Clay A-6		WH							
		WH	0.3B	27					
		WH							
	90.4								
Very soft, very moist to wet, grey, Silty Clay Loam to Silty Clay A-6	10.0	WH				35.0			
		WH	0.2B	28					
		WH							
	87.9								
Stiff, moist, brown mottled grey, Silty Clay Loam A-4		1							
		4	1.2S	22					
		5							
	85.4								
Soft, very moist, brown mottled grey, Silty Clay Loam A-4	15.0	1				40.0			
		2	0.4B	27					
		2							
	81.9								
Medium, moist to very moist, brown mottled grey, Silty Clay Loam A-4		WH							
		WH							
	80.4								
Stiff, moist, grey, Clay A7-6	20.0	2				45.0			
		4	1.7B	25					
		5							
	78.9								
Bottom of hole = 21.0 feet									
	25.0					50.0			

N-Std Pentr Test: 2" OD Sampler, 140# Hammer, 30" Fall (Type Fall. B-Bulge S-Shear E-Estimated P-Penetrometer)

Added 6-5-19