



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 30, 2024

SUBJECT FAI Route 290 (I-290)
Project NHPP-NYQR(889)
Section 2021-119-BR
Cook County
Contract No. 62P44
Item No. 2, June 14, 2024 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 107 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

UNDERPASS LIGHTING REMOVAL

Description. This work shall consist of the removal and disposal of an existing underpass lighting system at the location shown in the plans. All existing components (luminaires, junction boxes, cable, conduit, identification plates, etc.) for the existing underpass lighting system shall be removed. All removed equipment shall become the property of the Contractor and shall be disposed of offsite, in accordance with Department requirements.

Basis of Payment. This work shall be paid for at the contract unit price of lump sum for UNDERPASS LIGHTING REMOVAL which price included all labor and equipment necessary to complete this work.

BRICK PAVER REMOVAL AND REPLACEMENT

Description: This work consists of removal and replacement of brick accent pavers at locations as shown in the plans. Removal shall be performed in accordance with the applicable portions of Section 440 of the Standard Specifications. The existing subgrade shall be re-established with similar in-kind materials and grade. Removal shall be done so that bricks can be re-used. The Contractor will be required to clean and palletize bricks and store in a safe location. The Contractor shall be responsible for any damage to the bricks during removal, transportation and storage. If additional bricks are required due to damage they shall be replaced in the same size, style and color. If additional bricks remain after installation the Contractor shall be responsible for disposal of the bricks.

Method of Measurement: This work will be measured for payment in place per square foot.

Basis of Payment: This work will be paid for at the contract unit price per square foot for **REMOVAL AND REINSTALL BRICK PAVER.**

MULCH PLACEMENT FOR EXISTING WOODY PLANTS

This work shall be done in accordance with the applicable portion of Section 253.02 (c) and Section 1081.06 of the Standard Specifications for Road and Bridge Construction.

Description: This work shall consist of furnishing, transporting, and spreading an approved shredded hardwood bark mulch to the depth specified in areas as shown in the plans or as directed by the Engineer.

Revised 5/30/24