



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 5, 2024

SUBJECT FAP Route 335 (IL 176)
Project NHPP-LAA9(559)
Section FAP 335 23 Overlay
McHenry County
Contract No. 62V07
Item No. 12, June 14, 2024 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page ii of the Table of Contents to the Special Provisions
3. Added pages 123 & 124 to the Special Provisions
4. Revised sheets 1-6 & 24-31 of the Plans
5. Added sheets 15A-15D to the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TRAFFIC CONTROL AT AT-GRADE RR CROSSINGS 66

RAILROAD PROTECTIVE LIABILITY INSURANCE (BDE) 66

UP’S RIGHT OF ENTRY INSTRUCTIONS TO THE CONTRACTOR 68

CONTRACTOR’S RIGHR OF ENTRY AGREEMENT 68

RIGHT OF ENTRY APPLICATION 81

AGGREGATE SUBGRADE IMPROVEMENT (BDE) 82

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) 84

CEMENT, TYPE IL (BDE) 86

COMPENSABLE DELAY COSTS (BDE) 86

CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE) 90

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 92

FUEL COST ADJUSTMENT (BDE) 101

HOT-MIX ASPHALT (BDE) 104

HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE) 104

PERFORMANCE GRADED ASPHALT BINDER (BDE) 105

PORTLAND CEMENT CONCRETE (BDE) 111

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) 111

SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE) 112

SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE) 116

SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) 116

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 117

SUBMISSION OF PAYROLL RECORDS (BDE) 117

VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) 118

WEEKLY DBE TRUCKING REPORTS (BDE) 119

WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 119

WORKING DAYS (BDE) 121

MENTOR-PROTÉGÉ PROGRAM 122

COFFERDAM (TYPE 1) (IN-STREAM/WETLAND WORK) (D1) 123

PROPOSED MANHOLE/CATCH BASIN CONNECTION OVER EXISTING STORM SEWER 124

Revised 6/5/2024

COFFERDAM (TYPE 1) (IN-STREAM/WETLAND WORK) (D1)

Effective: January 1, 2019

Revised: August 15, 2022

Description. This work shall be performed in accordance with Section 502.06 of the Standard Specifications for Road and Bridge Construction, except as herein modified. The work shall consist of the preparation of an in-stream/wetland work plan and the installation, maintenance, removal and disposal of the temporary cofferdam(s) to isolate the work area from water within regulated wetlands and Waters of the U.S. (WOUS) in accordance with the authorized U.S. Army Corps of Engineers (USACE) Section 404 Permit and the General Conditions of the current Nationwide Permit Program.

Materials. Materials shall be in accordance with the USACE Section 404 Permit and General Conditions of the current Nationwide Permit Program.

Construction Requirements. Construction shall be in accordance with Article 502.06(a) of the Standard Specifications for Road and Bridge Construction and in accordance with the authorized USACE Section 404 Permit. For Cofferdam - Type 1, it is anticipated the design will be based on the flow requirement as shown in the plans and per the General Conditions of the current Nationwide Permit Program.

The Contractor shall be responsible for diverting the water flow from the construction area using a method meeting the approval of the Engineer and in accordance with the authorized USACE Section 404 Permit and General Conditions of the current Nationwide Permit Program.

This project requires a USACE Section 404 Permit prior to the start of work. All conditions of the Section 404 Permit must be followed. As a condition of the Section 404 Permit, the Contractor will be required to submit an In-Stream/Wetland Work Plan to the Department for approval. The USACE defines and determines in-stream/wetland work within the WOUS.

Guidelines on acceptable In-Stream/Wetland work techniques can be found on the USACE website: <https://www.lrc.usace.army.mil/Missions/Regulatory/Illinois/IL-Nationwide-Permits/>

Method of Measurement. This work will be measured for payment in units of Each where Each is defined as a plan detailed stage of bridge, culvert or other construction for which a temporary in-stream cofferdam(s) is required. If staged construction is not detailed/specified on the plans, this work will be measured as a total of One Each.

Basis of Payment. This work will be paid for at the contract unit price per each for COFFERDAM (TYPE 1) (IN-STREAM/WETLAND WORK).

Added 6/5/2024

PROPOSED MANHOLE/CATCH BASIN CONNECTION OVER EXISTING STORM SEWER

Description: This work shall consist of constructing catch basins, manholes, with frames and grates or lids, over an existing storm sewer at the location as shown on the plans. The work shall be performed in accordance with applicable portions of Sections 550 and 602 of the Standard Specifications.

Description: Materials shall be in accordance with applicable portions of Section 602 of the Standard Specifications.

Method of Measurement: This work will be measured for payment in units of each, of PROPOSED MANHOLE/CATCH BASIN CONNECTION OVER EXISTING STORM SEWER constructed in place.

Basis of Payment: This work will be paid for at the contract unit price each for PROPOSED MANHOLE/CATCH BASIN CONNECTION OVER EXISTING STORM SEWER.

Added 6/5/2024