



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 30, 2024

SUBJECT: FAI Route 74 (I-74)
Project NHPP-NQ29(512)
Section (48-29B)BR
Knox County
Contract No. 68E35
Item No. 38, June 14, 2024 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page i of the Table of Contents to the Special Provisions.
3. Revised page 14 of the Special Provisions.
4. Revised sheets 12, 19, 26, and 27 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

LOCATION OF PROJECT 1
DESCRIPTION OF PROJECT 1
DESCRIPTION OF PROJECT (CONTINUED)..... 2
CONSTRUCTION LAYOUT RESPONSIBILITY 2
CONSTRUCTION LAYOUT UTILIZING GPS EQUIPMENT..... 2
CONSTRUCTION LAYOUT EQUIPMENT 3
UTILITIES – LOCATIONS/INFORMATION ON PLANS 4
LOCATION OF UNDERGROUND STATE MAINTAINED FACILITIES 4
INTERIM COMPLETION DATES WITH WORKING DAYS 4
WORKING RESTRICTIONS & TRAFFIC CONTROL/STAGING NOTES..... 5
EMBANKMENT (RESTRICTIONS)..... 6
MOWING 7
SUBGRADE TREATMENT 8
TEMPORARY PAVEMENT..... 8
HOT-MIX ASPHALT SURFACE COURSE SURFACE TESTS 9
HOT-MIX ASPHALT SURFACE REMOVAL, 2" 9
PAVEMENT DRAINAGE AFTER COLD MILLING 12
HOT-MIX ASPHALT JOINT TRIMMING..... 12
HOT-MIX ASPHALT SHOULDER RESURFACING REQUIRED TO BE CONSTRUCTED
SIMULTANEOUSLY WITH MAINLINE PAVING 13
PAVEMENT REMOVAL (SPECIAL)..... 14
DOUBLE EXPANSION JOINT 4" 14
BRIDGE APPROACH PAVEMENT CONNECTOR (SPECIAL)..... 15
DOUBLE REINFORCED CONCRETE SLAB..... 15
SURFACE REMOVAL, VARIABLE DEPTH (SPECIAL)..... 15
SHOULDER RUMBLE STRIP REMOVAL..... 18
GRANULAR BACKFILL FOR STRUCTURES..... 18
PCC PLACEMENT BY PUMP REQUIREMENTS 19
REMOVE EXISTING FLARED END SECTION..... 19
REMOVE CONCRETE HEADWALLS FOR PIPE DRAINS 20
PIPE UNDERDRAIN REMOVAL..... 20

PAVEMENT REMOVAL (SPECIAL)

Description. This work shall consist of the complete removal of existing pavement, double expansion joints, and double reinforced slabs.

CONSTRUCTION REQUIREMENTS

Materials resulting from the removal of existing pavement and appurtenances as herein specified shall be disposed of according to Article 202.03 of the Standard Specifications.

Method of Measurement. This work will be measured for payment in Square Yards.

Basis of Payment. This work will be paid for at the contract unit price per Square Yard for PAVEMENT REMOVAL (SPECIAL).

DOUBLE EXPANSION JOINT 4"

Description. This work shall consist of construction of Portland cement concrete pavement, double transverse expansion joint, dowel bars, welded wire reinforcement, and sub-base according to the details on the plans, Highway Standard 420001, and the applicable portions of Sections 311 and 420 of the Standard Specifications.

Method of Measurement. This work will be measured for payment in place by measuring the area of pavement removal and replacement, and the area computed in Square Yards.

Basis of Payment. This work will be paid for at the contract unit price per Square Yard for DOUBLE EXPANSION JOINT 4".

The cost for sub-base granular material will not be paid for separately but shall be included in the contract unit price for Double Expansion Joint 4".

Revised May 30, 2024