



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 5, 2024

SUBJECT FAU Route 1238 (IL 176)
Project STP-N03T(716)
Section FAU 1238 23 Overlay
Lake County
Contract No. 62U77
Item No. 112, June 14, 2024 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 44 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

CONCRETE CURB, TYPE B, (SPECIAL)

This work shall consist of furnishing all labor, equipment, and material for the installation of CONCRETE CURB, TYPE B, SPECIAL in accordance with Section 606 of the Standard Specifications, except as modified herein.

Top of concrete curb shall be flush with top of paver pavement as shown in the details.

Steel reinforcement bars shall not be paid for separately but included in the cost of the concrete curb.

This work shall be measured in total length and paid for at the contract unit price per foot for CONCRETE CURB, TYPE B (SPECIAL) and shall include all labor, tools, materials and equipment needed to complete this work.

CONCRETE STEPS

Description: This work shall consist of constructing concrete steps to the lines, grades and details as shown in the Plans. This work shall be performed in accordance with Section 202 and 606 of the Standard Specifications. This work shall include excavation, subbase granular material (Type B), Portland cement concrete, and protective coat.

Standard Drawing 606001-08 shall be referenced for dowel and tie bar placement at the concrete steps location shown in the Plans.

Method of Measurement: Concrete steps shall be measured for payment based on the plan dimensions for the steps and the volume computed in cubic yards of concrete. The included subbase material and bars shall not be measured separately for payment.

Basis of Payment: This work will be paid for at the contract unit price per cubic yard for CONCRETE STEPS.

DECORATIVE STEEL RAILING

Description: This work shall consist of furnishing and erecting decorative steel fencing at the locations shown on the plans and as directed by the Engineer.

Materials: The railing shall be according to the DECORATIVE RAILING details as shown in the plans.

Method of Measurement: This work will be measured for payment in place in Feet. The length measured will be the overall length along the top longitudinal railing member through all posts and gaps.

Basis of Payment: This work will be paid for at the contract unit price per Foot for DECORATIVE STEEL RAILING.

Revised 6/5/2024