



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 30, 2024

SUBJECT: Route FAU 2733 (9th Avenue)
Section 23-00144-00-RS (Melrose Park)
Cook County
Contract No. 61K40
Item 118
June 14, 2024 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised Sheets 9, 19, 20 & 37 of the Plans.**
- 2. Revised the Schedule of Prices.**
- 3. Revised Page 2 of the Table of Contents to the Special Provisions.**
- 4. Revised Pages 52 – 54 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

ITEM	PAGE
CONNECTION TO EXISTING MANHOLE	18
STORM SEWERS, PVC PIPE, TYPE 1 10"	18
PVC COMBINED SEWER PIPE REPLACEMENT, 10"	18
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	19
UNCONTAMINATED SOIL CERTIFICATION	20
TRAFFIC CONTROL PLAN (D-1)	21
ADJUSTMENTS AND RECONSTRUCTIONS (D-1)	21
DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (D-1)	22
HOT-MIX ASPHALT - MIXTURE DESIGN VERIFICATION AND PROTECTION (D-1)	23
FRICTION AGGREGATE (D-1)	25
HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D-1)	27
PUBLIC CONVENIENCE AND SAFETY (D-1)	32
FAILURE TO COMPLETE PLANT CASE AND ESTABLISHMENT WORK ON TIME	32
SUPPLEMENTAL WATERING	33
AVAILABLE REPORTS	35
TRAFFIC SIGNAL GENERAL REQUIREMENTS	36
RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM (DELETED)	52
COILABLE NON-METALLIC	54
UNDERGROUND RACEWAYS	55
ROD AND CLEAN EXISTING CONDUIT	55
ELECTRIC CABLE	56
PEDESTRIAN SIGNAL POST	57
CONCRETE FOUNDATIONS	58
LIGHT EMITTING DIODE (LED) SIGNAL HEAD AND OPTICALLY PROGRAMMED LED SIGNAL HEAD	59
DETECTOR LOOP	62
DETECTOR LOOP REPLACEMENT AND/OR INSTALLATION	64
ACCESSIBLE PEDESTRIAN SIGNALS	67
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	70
REBUILD EXISTING HANDHOLE	71
LR 107-4	73
LR 1030-2	74
MWRDGC PERMIT	76

PAGE INTENTIONALLY LEFT BLANK

PAGE INTENTIONALLY LEFT BLANK

COILABLE NON-METALLIC CONDUIT

Effective: May 22, 2002

Revised: July 1, 2015

810.01TS

Description.

This work shall consist of furnishing and installing empty coilable non-metallic conduit (CNC).

General.

The CNC installation shall be in accordance with Sections 810 and 811 of the Standard Specifications except for the following:

Add the following to Article 810.03 of the Standard Specifications:

CNC meeting the requirements of NEC Article 353 shall be used for detector loop raceways to the handholes.

Add the following to Article 811.03 of the Standard Specifications:

On temporary traffic signal installations with detector loops, CNC meeting the requirements of NEC Article 353 shall be used for detector loop raceways from the saw-cut to 10 feet (3m) up the wood pole, unless otherwise shown on the plans