



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 22, 2024

SUBJECT FAI Route 55 (I-55)  
Project NHPP-D2C1(426)  
Section (84-2BR-1)D, BY, BP, BRR  
Sangamon County  
Contract No. 72K98

Item No. 140, June 14<sup>th</sup>, 2024 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices.
2. Revised page i of the Table of Contents of the Special Provisions.
3. Revised page 12 of the Special Provisions.
4. Revised sheets 9, 43-44, 48, 58, 65-72, 76, 86-88, 93-94, 96, and 109 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,


A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

## TABLE OF CONTENTS

LOCATION OF PROJECT .....	1
DESCRIPTION OF PROJECT .....	1
TRAFFIC CONTROL PLAN .....	1
STATUS OF UTILITIES TO BE ADJUSTED .....	3
COOPERATION BETWEEN CONTRACTORS.....	4
WORKING DAYS .....	4
REAL-TIME TRAFFIC CONTROL SYSTEM .....	5
HMA ANTI-STRIP ADDITIVE REQUIREMENTS .....	7
PAVEMENT STATIONING NUMBERS AND PLACEMENT .....	8
TEMPORARY CONCRETE BARRIER (TO REMAIN PERMANENTLY) .....	8
RELOCATE TEMPORARY CONCRETE BARRIER, STATE OWNED .....	9
REMOVE AND REINSTALL IMPACT ATTENUATORS.....	9
RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL .....	9
RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REPLACEMENT .....	10
STRUCTURAL STEEL REMOVAL.....	10
STRUCTURAL STEEL REPAIR .....	10
SLOPE WALL REPAIR.....	11
SLOPE WALL SLURRY PUMPING.....	11
REMOVAL OF EXISTING BEARINGS .....	12
HIGH LOAD MULTI-ROTATIONAL BEARINGS.....	13
JACK AND REMOVE EXISTING BEARINGS .....	19
JACKING EXISTING SUPERSTRUCTURE .....	20
MODULAR EXPANSION JOINT.....	21
CLEANING AND PAINTING CONTACT SURFACE AREAS OF EXISTING STEEL STRUCTURES.....	26
CLEANING AND PAINTING EXISTING STEEL STRUCTURES .....	32
CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES.....	54
STRUCTURAL REPAIR OF CONCRETE .....	78
DIAMOND GRINDING AND SURFACE TESTING BRIDGE SECTIONS .....	87
SLIPFORM PARAPET .....	92
STRUCTURAL ASSESSMENT REPORTS FOR CONTRACTOR'S MEANS AND METHODS.....	96
BRIDGE DECK CONSTRUCTION .....	99
BRIDGE DECK GROOVING (LONGITUDINAL) .....	100
HOT DIP GALVANIZING FOR STRUCTURAL STEEL.....	101
PREFORMED PAVEMENT JOINT SEAL.....	105



computed from field measurements.

Basis of Payment. This work will be paid for at the contract unit price per CUBIC YARD for SLOPE WALL SLURRY PUMPING.

### **REMOVAL OF EXISTING BEARINGS**

Description: This work shall consist of removal and proper disposal of the existing bearings at locations shown in the plans according to Article 501.05 of the Standard Specifications and the Jack and Remove Existing Bearings special provisions.

Basis of Payment:

This work will be paid for at the contract unit price EACH for REMOVAL OF EXISTING BEARINGS, which price shall include all equipment, materials and labor required to satisfactorily complete the work. The jacking and cribbing required to remove the load from the existing bearings is not included as part of this work but is included in payment for jacking existing superstructure.

1