

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				80% FED 20% STATE	
				BRIDGE URBAN	
				0047	
				SN 060-0124	
* 81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	500	500	
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	600	600	
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	600	600	
X0300062	GRAFFITI REMOVAL	SQ YD	76	76	
X0327487	TRIAxIAL GEOGRID REINFORCEMENT, TYPE I	SQ YD	468	468	
△ 58100210	FULL LANE SEALANT WATERPROOFING SYSTEM	SQ YD	1,722	1,722	
X2810103	STONE RIPRAP, CLASS A1 (SPECIAL)	TON	468	468	
△ X5200101	REMOVE EXISTING JOINT	FOOT	155	155	
X7011800	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1	
X7830050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	5	5	
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	12	12	
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	8,000	8,000	
Z0001905	STRUCTURAL STEEL REPAIR	POUND	6,950	6,950	
Z0003802	REMOVAL OF EXISTING BEARINGS	EACH	16	16	
Z0007101	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1	

* SPECIALTY ITEM

△ REVISED 5-22-2024

REV. - MS

MODEL: Default
FILE NAME: H:\P220022 - IDOT DB PH 1 & 2 VAR - VAR (PTE)194-05\11W0 7 - IL 111 Bridge Repairs SN 060-124 - Updated_Scope\CADD\crossstation\CADD Drawings\087846-shs-S00.dgn



USER NAME = zachary.hresko
DESIGNED -
DRAWN -
PLOT SCALE = 100.0000' / in.
CHECKED -
DATE -

DESIGNED -
REVISIED -
CHECKED -
DATE -

REVISIED -
REVISIED -
REVISIED -
REVISIED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 5 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
582	6VBR-1	MADISON	68	7
			CONTRACT NO. 76P46	
ILLINOIS FED. AID PROJECT				

ILLINOIS DESIGN FIRM LICENSE NO.: 184.001115