

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		JO DAVIESS	39	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

DESCRIPTION	LOCATION	SIDEWALK REMOVAL SQ FT	SIDEWALK REMOVAL SPECIAL SQ FT	PC CONCRETE SIDEWALK, 4" SQ FT	PC CONCRETE SIDEWALK, 5" COLORED SQ FT	BRICK PAVER SIDEWALK W/RIGID BASE SQ FT	BRICK PAVER SIDEWALK W/FLEXIBLE BASE SQ FT	WOOD SIDEWALK SQ FT	DETECTABLE WARNINGS SQ FT
First Lady's Park to Alley	50+00 to 51+47			600.5					
Trail #2	20+00						125		
Trail #2	21+74 70' RT			14					
Grant's Home	30+00 to 30+25.5		124.5			125			
Grant's Home	30+30 LT		92	90.3			64.5		
Grant's Home	30+35.51 LT		562.9	64.4			337		
Grant's Home	30+35.51 RT						110.5		
Grant's Home	30+44 to 31+13.67		295.8				346		
Grant's Home	31+13.67 AH RT			10.8					
Grant's Home	31+13.67 BK RT						28.9		
Grant's Home	31+13.67 to 33+33.67		1037.5				1283.1		
Grant's Home	Front Walk	290	214.8	290				204	
Washburne House	Third/Decatur (SW Quad)				18				25
Washburne House	Third St.	25	432.3		287			85	
Washburne House	Decatur St.		440		440				
IHPA Site Office	Carriage Walk		80		97				
IHPA Site Office	4th St.		405		843				
<b>TOTAL</b>		<b>315</b>	<b>3685</b>	<b>1070</b>	<b>1685</b>	<b>125</b>	<b>2295</b>	<b>289</b>	<b>25</b>

DESCRIPTION	LOCATION	AGGREGATE, BASE COURSE, TYPE B TON	STONE SURFACE SPECIAL SQ YD	STONE SEATING SQ FT
First Lady's Park to Alley	50+00 to 51+47	21.5		
Trail #1	40+03 to 42+23.9	33.2	122.7	
Trail #1	40+73	1.8		6
Trail #1	Extension to East	22.1	81.7	
Trail #2	Statue	12.1	43.9	18
Trail #2	20+05 to 21+67.11	24.4	90.1	
Trail #2	21+67.11 to 22+92	18.8	70.9	
Trail #3	10+02.5 to 11+93	28.6	105.8	
Trail #3	10+52 RT	5.8	21	18
Grant's Home	30+30 RT	2.3		
Grant's Home	30+35.51 BK RT	1.6		
Grant's Home	31+13.67 BK RT	5.5		
Grant's Home	31+13.67 AH RT	0.3		
Washburne House	Carriage Walk	2.1		
Washburne House	Third St.	7.2		
Washburne House	Third/Decatur	0.5		
Washburne House	Decatur St.	11.2		
IHPA Site Office	Carriage Walk	2.4		
IHPA Site Office	4th St.	23.9		
Subtotal		225.3	536.1	
<b>TOTAL</b>		<b>230</b>	<b>540</b>	<b>42</b>

INTERPRETIVE SIGNAGE COMPLETE	
DESCRIPTION	EACH
LT STA 10+59.5	1
RT STA 10+82.0	1
RT STA 40+77.0	1
<b>TOTAL</b>	<b>3</b>

DESCRIPTION	LOCATION	HANDRAIL REMOVAL FOOT	STEP REMOVAL EACH	CONCRETE STEPS SQ FT	COLORED CONCRETE STEPS EACH	BRICK SIDEWALK STEPS EACH	WOOD STEPS EACH	PIPE HANDRAIL FOOT	PIPE HANDRAIL SPECIAL, TYPE 1 FOOT	PIPE HANDRAIL SPECIAL, TYPE 2 FOOT
First Lady's Park to Alley	50+04 to 51+46 LT/RT							281		
First Lady's Park to Alley	50+00 to 51+49.25			260						
Grant's Home	30+00 to 30+04.6 LT/RT									10
Grant's Home	30+04.6 to 30+21.5 LT/RT									34
Grant's Home	30+30 LT								21	
Grant's Home	30+35.51 BK LT								19	
Grant's Home	31+13.67 AH RT		10			10				24
Grant's Home	31+13.67 BK RT	17	15			15				32
Grant's Home	31+16.67 to 32+15.67/LT									99
Grant's Home	31+16.67 to 33+32.67 LT/RT									216
Grant's Home	31+13.67 to 33+36.3 LT/RT	429								
Grant's Home	32+31 to 32+37/LT									16
Grant's Home	32+41 to 33+31/LT									90
Washburne House	Carriage Walk		2				2			
IHPA Site Office	Carriage Walk	48	4		4			12		
IHPA Site Office	4th St.	56								
<b>TOTAL</b>		<b>550</b>	<b>31</b>	<b>260</b>	<b>4</b>	<b>25</b>	<b>2</b>	<b>293</b>	<b>40</b>	<b>521</b>

DESCRIPTION	LOCATION	PIPE CULVERT SPECIAL, 6" FOOT	STORM SEWER, CLASS B, TYPE 1, 6 FOOT	INLETS, SPECIAL EACH	CONCRETE HEADWALL FOR PIPE DRAINS EACH	INLET AND PIPE PROTECTION EACH
Trail #1	40+85.54/LT			1		1
Trail #1	40+85.54/LT & RT		16			
Trail #1	40+85.54/ RT				1	
Trail #1	41+41.2/LT			1		1
Trail #1	41+41.2/ LT & RT		18			
Trail #1	41+41.2/RT				1	
Trail #2	22+20.8/RT			1		1
Trail #2	22+20.85/LT & RT		21			
Trail #2	22+20.8/RT				1	
Trail #3	10+56.85/RT			1		1
Trail #3	10+30 TO 10+56.85/RT		22			
Trail #3	10+30/RT				1	
Grant's Home	30+16.75			1		1
Grant's Home	30+16.75 TO 30+06.23		32			
Grant's Home	30+06.23/LT				1	
Gift Shop	30+40.73/LT			1		1
Gift Shop	30+16.75 TO 30+40.73/LT	14	34			
IHPA Site Office	4TH STREET				2	1
<b>TOTAL</b>		<b>14</b>	<b>143</b>	<b>6</b>	<b>7</b>	<b>7</b>

DESCRIPTION	LOCATION	WATER SERVICE LINES, 1" FOOT	WATER VALVES, 1" EACH	WATER HYDRANT EACH	RPZ BACKFLOW PREVENTER, 1" EACH	CORPORATION STOP, 1" EACH	WATER METER INSTALLED EACH	VALVE BOX FRAMES TO BE ADJUSTED EACH
Trail #1	41+68.5' LT							
Trail #1	41+68.5/LT to 21+01/RT	193		1				
Trail #2	20+95/62' RT						1	
Trail #2	21+01/RT to 21+08.5/RT	13						
Trail #2	21+08.5/RT to 21+15/RT	22						
Trail #2	21+09.5/76' RT				1			
Trail #2	21+15/93' RT					1		
Trail #3	11+63/37' RT	17		1				
Trail #3	11+63/RT to 11+74/RT							
Trail #3	11+74/47' RT		1					
Trail #3	11+74/51' RT		1					
Grant's Home	30+62/RT							1
Washburne House	Third St.							1
IHPA Site Office	4th St.							3
<b>TOTAL</b>		<b>245</b>	<b>2</b>	<b>2</b>	<b>1</b>	<b>1</b>	<b>1</b>	<b>5</b>

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		IDOT / IHPA GALENA STATE HISTORIC SITES SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE: 12/18/06 DRAWN BY: JJ CHECKED BY: PJM