

SUMMARY OF QUANTITIES			90% FED./10% STATE					SUMMARY OF QUANTITIES			90% FED./10% STATE								
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						
				I000-1A	Y031-1F	Y031-3D								I000-1A	Y031-1F	Y031-3D			
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	499		499					* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2				
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	34		34					* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	1		1				
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	10		10					* 88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1				
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	69		69					* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1		1				
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	349		349					* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8		8				
* 81400100	HANDHOLE	EACH	3		3					* 88500100	INDUCTIVE LOOP DETECTOR	EACH	5		5				
* 81400200	HEAVY-DUTY HANDHOLE	EACH	5		5					* 88600100	DETECTOR LOOP, TYPE I	FOOT	512		512				
* 81400300	DOUBLE HANDHOLE	EACH	1		1					* 88700200	LIGHT DETECTOR	EACH	4			4			
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	538		538					* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1			1			
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1					* A2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5					
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	612		612					* A2005616	TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM), 2" CALIPER, BALLED AND BURLAPPED	EACH	9	9					
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2175		2175					* A2007114	TREE, QUERCUS RUBRA (RED OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	6	6					
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	218		218					* A2007920	TREE, TILIA AMERICANA REDMOND (REDMOND AMERICAN LINDEN), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	7	7					
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1359		1359					* B2000764	TREE, AMELANCHIER X GRANDIFLORA AUTUMN BRILLIANCE (AUTUMN BRILLIANCE SERVICE BERRY), 5' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	45	45					
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	54		54					* B2002166	TREE, CRATAEGUS VIRDIS (GREEN HAWTHORN), 6' HEIGHT, MULTI-STEM, BALLED AND BURLAPPED	EACH	7	7					
* 87700130	STEEL MAST ARM ASSEMBLY AND POLE, 18 FT.	EACH	1		1					* C2001536	SHRUB, CORNUS RACEMOSA (GREY DOGWOOD), 3' HEIGHT, BALLED AND BURLAPPED	EACH	100	100					
* 87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1					* C2008218	SHRUB, ROSA NEARLY WILD (NEARLY WILD SHRUB ROSE), 18" HEIGHT, CONTAINER	EACH	45	45					
* 87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1		1					* K0026850	PERENNIAL PLANT CARE	SQ YD	600	600					
* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1		1					* K0029000	PERENNIAL PLANTS, WOODLAND TYPE	UNIT	11	11					
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4					* K0036120	MULCH PLACEMENT 4"	SQ YD	1850	1850					
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	60		60					X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8					
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	7		7														

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 ILL 171 (ARCHER AVE.)
 AT ASHBURY DR. AND 131ST ST.
 SUMMARY OF QUANTITIES

PLOT DATE: 5/3/2007

5/3/2007