

SUMMARY OF QUANTITIES

| 16ROUTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NUMBER |
|---------|---------------|--------|--------------|--------------|
| FAP 348 | 3128-Z-HB-1-I | COOK | 16 | 3 |

CONSTRUCTION TYPE CODE SFTY-2A

CONTRACT: 60B25
URBAN-100/STATE

| CODE NO. | DESCRIPTION | UNIT | TOTAL QUANTITIES |
|----------|--|--------|------------------|
| 58700300 | CONCRETE SEALER | SQ FT | 7155 |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 1 |
| 67100100 | MOBILIZATION | L SUM | 1 |
| 70101800 | TRAFFIC CONTROL AND PROTECTION (SPECIAL) | L SUM | 1 |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 |
| X0320887 | POLYMER CONCRETE | CU FT | 15.5 |
| X0321744 | SILICONE JOINT SEALER, 2" | FOOT | 148 |
| X0322467 | TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE | SQ FT | 24 |
| X0323076 | SILICONE JOINT SEALER, 1 3/4" | FOOT | 112 |
| X0325303 | STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES) | SQ FT | 79 |
| X0325305 | STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES) | SQ FT | 1160 |
| Z0001700 | APPROACH SLAB REPAIR (FULL DEPTH) | SQ YD | 6 |
| Z0048665 | RAILROAD PROTECTIVE LIABILITY INSURANCE | L SUM | 1 |
| Z0073200 | TEMPORARY SHORING AND CRIBBING | EACH | 8 |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

Rev.