

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	BRIDGE SN 016-0522 STATE 100% SFTY-2A					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.6	0.6					
40600300	AGGREGATE (PRIME COAT)	TON	3	3					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.4	0.4					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	27	27					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	61	61					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	203	203					
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	385	385					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	156	156					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	949	949					
44000705	BARRIER MEDIAN REMOVAL	SO FT	120	120					
45000130	RELIEF JOINT 4"	FOOT	120	120					
50157300	PROTECTIVE SHIELD	SO YD	1552	1552					
50300300	PROTECTIVE COAT	SO YD	230	230					
60623800	CONCRETE BARRIER MEDIAN	SO FT	120	120					
67100100	MOBILIZATION	L SUM	1	1					
70102670	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601 (SPECIAL)	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	660	660					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2112	2112					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1045	1045					
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	592	592					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	23	23					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	23	23					
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SO FT	48	48					

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	BRIDGE SN 016-0522 STATE 100% SFTY-2A					
X0323077	SILICONE JOINT SEALER, 2 3/4"	FOOT	160	160					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
X7030100	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III	FOOT	6400	6400					
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	74	74					
Z0016200	DECK SLAB REPAIR (PARTIAL)	SO YD	167	167					
X0325775	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	6400	6400					
X0322066	PROTECTIVE SHIELD (PERMANENT)	SQ YD	1458	1458					
Z0001700	APPROACH SLAB REPAIR (FULL DEPTH)	SQ YD	17	17					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1					
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	18	18					

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev.