

F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) WRS-2	WILL	228	6
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY I000-2A	BLACK RD 099-0209 SFTY-2A	CATON FARM 099-0210 X231-2A	SIGNING
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3			
63200310	GUARDRAIL REMOVAL	FOOT	10,200	10,200			
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	125	125			
63500105	DELINEATORS	EACH	114	114			
63700805	CONCRETE BARRIER TRANSITION	FOOT	397	397			
63700900	CONCRETE BARRIER BASE	FOOT	16,829	16,829			
64200105	SHOULDER RUMBLE STRIP	FOOT	70,508	70,508			
67100100	MOBILIZATION	L SUM	1	1			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18	18			
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	221,591	221,591			
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	20,707	20,707			
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	9,102	9,102			
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	823	823			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	50,982	50,982			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	34,770	34,770			
72000200	SIGN PANEL - TYPE 2	SQ FT	183				183
72000300	SIGN PANEL - TYPE 3	SQ FT	2,129				2,129
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	9				9
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	11				11
72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	20				20
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	2,018				2,018
72600100	MILE POST MARKER ASSEMBLY	EACH	7				7
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1,546				1,546
73000100	WOOD SIGN SUPPORT	FOOT	280				280
73400100	CONCRETE FOUNDATIONS	CU YD	3.9				3.9
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	5				5
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	5				5
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	70,477	70,477			
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4,197	4,197			
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,020	2,020			
78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	1,467	1,467			
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	18,801	18,801			
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	45,674	45,674			
78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	28,690	28,690			
78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	4,354	4,354			
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	439	439			
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,884	1,884			
78100300	REPLACEMENT REFLECTOR	EACH	388	388			
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	6,612	6,612			
78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16			
78200530	BARRIER WALL MARKERS, TYPE C	EACH	434	434			
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	18,347	18,347			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	872	872			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	785	785			
X0322323	WEED CONTROL, TEASEL	GALLON	2.5	2.5			

URBAN
**

* SPECIALTY ITEMS
** URBAN, 90% FEDERAL, 10% STATE (SEE NOTE)

NOTE:


TYPE 3 SIGN PANELS WHICH REQUIRE TYPE ZZ SHEETING WILL BE 100% PAID FOR BY STATE FUNDS. THE REST WILL BE PAID FOR BY 90% FEDERAL FUNDS AND 10% STATE FUNDS. A QUANTITY OF 952 SQ FT OF ITEM NO. 72000300, SIGN PANEL - TYPE 3 REQUIRES TYPE ZZ RETROREFLECTIVE SHEETING.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (BLACK ROAD TO U.S. 30)
WIDENING AND RESURFACING

SUMMARY OF QUANTITIES III

SCALE: N.T.S. DRAWN BY AG
DATE 03/22/07 CHECKED BY DDH



TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

PLOT DATE = 03/22/07
FILE NAME = 60B46.PLT
PLOT SCALE = 1/4"=1'-0"
USER NAME = WISENS