

SCHEDULE OF QUANTITIES

CONTRACT NO. 60B46

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) WRS-2	WILL	228	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTINUED FROM SHEET 12

HOT-MIX ASPHALT REPLACEMENT OVER PATCHES						TOTAL 1636	TON
STATION	LENGTH (FT)	LENGTH +20%+2' (FT)	WIDTH (FT)	BIT REMOV/PATCH (SQ YD)	TONS/ SQ YD 3" THICK	SUBTOTAL	
577+75.80	4.00	6.80	7.00	5.29	0.196	1.037	
	4.00	6.80	5.00	3.78	0.196	0.740	
579+77.20	4.00	6.80	7.00	5.29	0.196	1.037	
	4.00	6.80	5.00	3.78	0.196	0.740	
580+78.00	4.00	6.80	7.00	5.29	0.196	1.037	
	4.00	6.80	5.00	3.78	0.196	0.740	
581+80.70	4.00	6.80	7.00	5.29	0.196	1.037	
	4.00	6.80	5.00	3.78	0.196	0.740	
	4.00	6.80	7.00	5.29	0.196	1.037	
	4.00	6.80	5.00	3.78	0.196	0.740	
585+41.80	4.00	6.80	5.00	3.78	0.196	0.740	
N.B. LANE 2							
TOTAL LENGTH	0.00	0.00	0.00	0.00	0.196	0.00	
CLASS D PATCHES TYPE II, 10"							
S.B. LANE 1							
0+00.00	10.00	14.00	7.00	10.89	0.196	2.134	
584+74.63	10.00	14.00	5.00	7.78	0.196	1.524	
583+81.12	9.00	12.80	7.00	9.96	0.196	1.951	
583+74.55	9.00	12.80	5.00	7.11	0.196	1.394	
0+00.00	7.00	10.40	7.00	8.09	0.196	1.585	
580+79.80	7.00	10.40	7.00	8.09	0.196	1.585	
579+80.02	8.00	11.60	7.00	9.02	0.196	1.768	
579+73.77	8.00	11.60	5.00	6.44	0.196	1.263	
578+80.16	7.00	10.40	7.00	8.09	0.196	1.585	
0+00.00	10.00	14.00	7.00	10.89	0.196	2.134	
576+72.40	10.00	14.00	5.00	7.78	0.196	1.524	
574+71.74	9.00	12.80	7.00	9.96	0.196	1.951	
0+00.00	9.00	12.80	5.00	7.11	0.196	1.394	
572+80.15	10.00	14.00	7.00	10.89	0.196	2.134	
572+73.86	10.00	14.00	5.00	7.78	0.196	1.524	
0+00.00	10.00	14.00	7.00	10.89	0.196	2.134	
571+75.74	10.00	14.00	5.00	7.78	0.196	1.524	
571+32.22	7.00	10.40	7.00	8.09	0.196	1.585	
570+82.34	8.00	11.60	7.00	9.02	0.196	1.768	
570+77.58	8.00	11.60	5.00	6.44	0.196	1.263	
562+81.93	9.00	12.80	7.00	9.96	0.196	1.951	
562+73.76	9.00	12.80	5.00	7.11	0.196	1.394	
559+81.82	8.00	11.60	7.00	9.02	0.196	1.768	
559+73.82	8.00	11.60	5.00	6.44	0.196	1.263	
558+80.74	7.00	10.40	7.00	8.09	0.196	1.585	
555+78.94	9.00	12.80	7.00	9.96	0.196	1.951	
555+72.90	9.00	12.80	5.00	7.11	0.196	1.394	
552+74.22	8.00	11.60	7.00	9.02	0.196	1.768	
0+00.00	8.00	11.60	5.00	6.44	0.196	1.263	
551+78.04	7.00	10.40	7.00	8.09	0.196	1.585	
550+84.07	10.00	14.00	7.00	10.89	0.196	2.134	
550+74.28	10.00	14.00	5.00	7.78	0.196	1.524	
549+79.49	8.00	11.60	7.00	9.02	0.196	1.768	
549+74.64	8.00	11.60	5.00	6.44	0.196	1.263	
548+79.15	8.00	11.60	7.00	9.02	0.196	1.768	
548+74.56	8.00	11.60	5.00	6.44	0.196	1.263	
547+79.11	8.00	11.60	7.00	9.02	0.196	1.768	
547+74.38	8.00	11.60	5.00	6.44	0.196	1.263	
546+80.18	8.00	11.60	7.00	9.02	0.196	1.768	
546+75.12	8.00	11.60	5.00	6.44	0.196	1.263	
545+82.11	9.00	12.80	7.00	9.96	0.196	1.951	
545+74.81	9.00	12.80	5.00	7.11	0.196	1.394	
543+82.89	9.00	12.80	7.00	9.96	0.196	1.951	
543+74.48	9.00	12.80	5.00	7.11	0.196	1.394	
0+00.00	10.00	14.00	7.00	10.89	0.196	2.134	
541+74.11	10.00	14.00	5.00	7.78	0.196	1.524	
540+83.83	7.00	10.40	7.00	8.09	0.196	1.585	
538+80.53	7.00	10.40	7.00	8.09	0.196	1.585	
537+80.98	8.00	11.60	7.00	9.02	0.196	1.768	
537+76.09	8.00	11.60	5.00	6.44	0.196	1.263	
532+83.86	10.00	14.00	7.00	10.89	0.196	2.134	
532+74.08	10.00	14.00	5.00	7.78	0.196	1.524	
529+83.35	6.00	9.20	7.00	7.16	0.196	1.402	
528+82.50	9.00	12.80	7.00	9.96	0.196	1.951	
528+75.69	9.00	12.80	5.00	7.11	0.196	1.394	
0+00.00	7.00	10.40	7.00	8.09	0.196	1.585	
525+81.65	8.00	11.60	7.00	9.02	0.196	1.768	
525+76.99	8.00	11.60	5.00	6.44	0.196	1.263	
523+80.52	8.00	11.60	7.00	9.02	0.196	1.768	
523+76.62	8.00	11.60	5.00	6.44	0.196	1.263	
522+81.74	8.00	11.60	7.00	9.02	0.196	1.768	
522+76.13	8.00	11.60	5.00	6.44	0.196	1.263	
0+00.00	11.00	15.20	7.00	11.82	0.196	2.317	
518+74.73	11.00	15.20	5.00	8.44	0.196	1.655	
517+83.34	8.00	11.60	7.00	9.02	0.196	1.768	
517+76.01	8.00	11.60	5.00	6.44	0.196	1.263	
513+83.41	9.00	12.80	7.00	9.96	0.196	1.951	
513+74.76	9.00	12.80	5.00	7.11	0.196	1.394	
0+00.00	9.00	12.80	7.00	9.96	0.196	1.951	

CONTINUED IN NEXT COLUMN

CONTINUED FROM PREVIOUS COLUMN

STATION	LENGTH (FT)	LENGTH +20%+2' (FT)	WIDTH (FT)	BIT REMOV/PATCH (SQ YD)	TONS/ SQ YD 3" THICK	SUBTOTAL	
512+76.12	9.00	12.80	5.00	7.11	0.196	1.394	
493+82.37	6.00	9.20	7.00	7.16	0.196	1.402	
489+83.44	7.00	10.40	7.00	8.09	0.196	1.585	
485+83.06	8.00	11.60	7.00	9.02	0.196	1.768	
485+75.72	8.00	11.60	5.00	6.44	0.196	1.263	
484+82.39	8.00	11.60	7.00	9.02	0.196	1.768	
484+74.39	8.00	11.60	5.00	6.44	0.196	1.263	
483+83.47	9.00	12.80	7.00	9.96	0.196	1.951	
483+74.48	9.00	12.80	5.00	7.11	0.196	1.394	
482+81.95	6.00	9.20	7.00	7.16	0.196	1.402	
481+82.37	9.00	12.80	7.00	9.96	0.196	1.951	
481+76.36	9.00	12.80	5.00	7.11	0.196	1.394	
479+82.53	9.00	12.80	7.00	9.96	0.196	1.951	
479+76.69	9.00	12.80	5.00	7.11	0.196	1.394	
478+82.53	8.00	11.60	7.00	9.02	0.196	1.768	
478+75.33	8.00	11.60	5.00	6.44	0.196	1.263	
477+82.55	8.00	11.60	7.00	9.02	0.196	1.768	
477+75.49	8.00	11.60	5.00	6.44	0.196	1.263	
475+77.49	8.00	11.60	7.00	9.02	0.196	1.768	
0+00.00	8.00	11.60	5.00	6.44	0.196	1.263	
474+81.74	7.00	10.40	7.00	8.09	0.196	1.585	
473+83.36	9.00	12.80	7.00	9.96	0.196	1.951	
473+76.46	9.00	12.80	5.00	7.11	0.196	1.394	
472+82.69	8.00	11.60	7.00	9.02	0.196	1.768	
472+75.62	8.00	11.60	5.00	6.44	0.196	1.263	
471+82.74	9.00	12.80	7.00	9.96	0.196	1.951	
471+76.82	9.00	12.80	5.00	7.11	0.196	1.394	
470+83.06	10.00	14.00	7.00	10.89	0.196	2.134	
470+74.97	10.00	14.00	5.00	7.78	0.196	1.524	
469+82.78	9.00	12.80	7.00	9.96	0.196	1.951	
469+76.85	9.00	12.80	5.00	7.11	0.196	1.394	
0+00.00	9.00	12.80	7.00	9.96	0.196	1.951	
468+75.42	9.00	12.80	5.00	7.11	0.196	1.394	
467+82.63	9.00	12.80	7.00	9.96	0.196	1.951	
467+77.50	9.00	12.80	5.00	7.11	0.196	1.394	
466+82.73	9.00	12.80	7.00	9.96	0.196	1.951	
466+76.96	9.00	12.80	5.00	7.11	0.196	1.394	
465+83.67	10.00	14.00	7.00	10.89	0.196	2.134	
465+76.19	10.00	14.00	5.00	7.78	0.196	1.524	
462+76.11	13.00	17.60	7.00	13.69	0.196	2.683	
0+00.00	13.00	17.60	5.00	9.78	0.196	1.916	
456+81.67	8.00	11.60	7.00	9.02	0.196	1.768	
456+77.06	8.00	11.60	5.00	6.44	0.196	1.263	
455+85.50	13.00	17.60	7.00	13.69	0.196	2.683	
455+76.22	13.00	17.60	5.00	9.78	0.196	1.916	
454+70.26	6.00	9.20	7.00	7.16	0.196	1.402	
0+00.00	10.00	14.00	7.00	10.89	0.196	2.134	
453+60.78	10.00	14.00	5.00	7.78	0.196	1.524	
451+79.90	8.00	11.60	7.00	9.02	0.196	1.768	
451+72.24	8.00	11.60	5.00	6.44	0.196	1.263	
0+00.00	9.00	12.80	7.00	9.96	0.196	1.951	
450+61.23	9.00	12.80	5.00	7.11	0.196	1.394	
449+67.86	8.00	11.60	7.00	9.02	0.196	1.768	
449+60.41	8.00	11.60	5.00	6.44	0.196	1.263	
447+64.68	8.00	11.60	7.00	9.02	0.196	1.768	
447+59.58	8.00	11.60	5.00	6.44	0.196	1.263	
445+64.64	8.00	11.60	7.00	9.02	0.196	1.768	
445+56.96	8.00	11.60	5.00	6.44	0.196	1.263	
439+61.41	9.00	12.80	7.00	9.96	0.196	1.951	
439+53.78	9.00	12.80	5.00	7.11	0.196	1.394	
438+59.14	7.00	10.40	7.00	8.09	0.196	1.585	
432+55.04	6.00	9.20	7.00	7.16	0.196	1.402	
413+43.80	8.00	11.60	7.00	9.02	0.196	1.768	
413+38.71	8.00	11.60	5.00	6.44	0.196	1.263	
410+38.81	7.00	10.40	7.00	8.09	0.196	1.585	
S.B. LANE 2							
585+68.23	4.00	6.80	12.00	9.07	0.196	1.777	
584+77.69	4.00	6.80	12.00	9.07	0.196	1.777	
582+77.86</							