

SCHEDULE OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) WRS-2	WILL	228	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTINUED FROM SHEET 16

HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"					TOTAL 8343	SQ YD
LOCATION	FROM STATION	FROM OFFSET	TO STATION	TO OFFSET		SUB TOTALS
496+81.83	4	6.80	12			9.067
497+70.68	4	6.80	12			9.067
498+78.04	7	10.40	12			13.867
499+81.53	9	12.80	12			17.067
505+82.10	4	6.80	12			9.067
509+76.56	4	6.80	12			9.067
511+76.91	4	6.80	12			9.067
512+75.88	4	6.80	12			9.067
514+82.26	4	6.80	12			9.067
515+78.71	4	6.80	12			9.067
516+82.13	4	6.80	12			9.067
517+23.86	9	12.80	12			17.067
518+42.71	4	6.80	12			9.067
519+82.11	8	11.60	12			15.467
521+74.84	8	11.60	12			15.467
522+82.11	4	6.80	12			9.067
523+81.57	4	6.80	12			9.067
525+75.16	4	6.80	12			9.067
527+74.23	4	6.80	12			9.067
528+00.93	4	6.80	12			9.067
528+47.18	4	6.80	12			9.067
528+64.72	4	6.80	12			9.067
528+77.68	4	6.80	12			9.067
531+80.90	4	6.80	12			9.067
534+80.68	4	6.80	12			9.067
535+80.22	4	6.80	12			9.067
537+80.61	4	6.80	12			9.067
538+84.03	4	6.80	12			9.067
543+76.86	4	6.80	12			9.067
544+79.70	8	11.60	12			15.467
548+77.05	4	6.80	12			9.067
556+76.70	5	8.00	12			10.667
558+22.55	4	6.80	12			9.067
563+79.42	4	6.80	12			9.067
568+71.67	4	6.80	12			9.067
569+76.46	4	6.80	12			9.067
570+74.26	4	6.80	12			9.067
577+75.80	4	6.80	12			9.067
S.B. LANE 1						
0+00.00	0.00	0.00	0.00			0.00
S.B. LANE 2						
583+73.14	10.00	14.00	12.00			18.667
580+73.77	14.00	18.80	12.00			25.067
579+73.77	10.00	14.00	12.00			18.667
578+73.32	10.00	14.00	12.00			18.667
574+70.82	10.00	14.00	12.00			18.667
567+75.20	12.00	16.40	12.00			21.867
566+72.98	11.00	15.20	12.00			20.267
565+74.40	10.00	14.00	12.00			18.667
562+73.76	10.00	14.00	12.00			18.667
559+73.82	10.00	14.00	12.00			18.667
550+69.42	15.00	20.00	12.00			26.667
545+74.81	10.00	14.00	12.00			18.667
540+74.54	10.00	14.00	12.00			18.667
532+74.08	10.00	14.00	12.00			18.667
492+66.14	13.00	17.60	12.00			23.467
488+74.79	12.00	16.40	12.00			21.867
486+75.50	11.00	15.20	12.00			20.267
472+75.62	10.00	14.00	12.00			18.667
459+76.75	11.00	15.20	12.00			20.267
N.B. LANE 1						
0+00.00	0.00	0.00	0.00			0.00
N.B. LANE 2						
539+72.64	11.00	13.20	12.00			17.60
CLASS D PATCHES TYPE III, 10"						
S.B. LANE 1						
462+72.74	16.00	21.20	25.6			60.302
455+74.34	18.00	23.60	28.8			75.520
S.B. LANE 2						
000+00.00	0.00	0.00	0			0.00
N.B. LANE 1						
000+00.00	0.00	0.00	0			0.00
N.B. LANE 2						
553+76.53	24.00	30.80	38.4			131.413
CLASS D PATCHES TYPE IV, 10"						
S.B. LANE 1						
462+72.74	16.00	21.20	12.00			28.267
455+74.34	18.00	23.60	12.00			31.467
S.B. LANE 2						
000+00.00	0.00	0.00	0.00			0.000
N.B. LANE 1						
000+00.00	0.00	0.00	0.00			0.000
N.B. LANE 2						
553+76.53	24.00	30.80	12.00			41.067

CONTINUED IN THE NEXT COLUMN

CONTINUED FROM PREVIOUS COLUMN

LOCATION	FROM STATION	FROM OFFSET	TO STATION	TO OFFSET	SUB TOTALS
Inc Qty of Pat by 60% (20%/Yr Sin Patch Surv Compl In 2005)					
3083.67					
LOCATION	STA.	OFFSET	STA.	OFFSET	SQ YD
STORM SEWER LATERALS					
SB	403+71.00	20.00 LT	403+71.00	44.00 LT	20.00
SB	405+08.20	20.00 LT	405+05.32	44.00 LT	20.00
NB	480+00.00	44.00 RT	480+00.00	20.00 RT	20.00
SB	504+08.00	20.00 LT	504+08.00	44.00 LT	18.44
SB	510+48.00	20.00 LT	510+48.00	44.00 LT	21.56
SB	556+76.44	20.00 LT	556+77.41	44.00 LT	20.00

BITUMINOUS CONCRETE SHOULDER REMOVAL					TOTAL 22618	SQ YD
DIRECTION	FROM STA.	TO STA.	MEASURED AREA (SQ FT)		SUBTOTALS (SQ YD)	
S.B.	402+65.07	457+00.00	38,497.00		4277.44	
S.B.	457+00.00	491+42.70	18,396.00		2044.00	
S.B.	492+02.49	532+00.00	20,584.00		2287.11	
S.B.	532+00.00	547+00.00	5,202.00		578.00	
S.B.	547+00.00	552+04.61	2,155.00		239.44	
S.B.	552+57.58	573+00.00	10,189.00		1132.11	
N.B.	402+65.07	427+00.00	10,469.00		1163.22	
N.B.	427+00.00	457+00.00	11,094.00		1232.67	
N.B.	457+00.00	491+79.57	13,894.00		1543.78	
N.B.	492+02.34	502+00.00	4,128.00		458.67	
N.B.	502+00.00	532+00.00	25,311.00		2812.33	
N.B.	532+00.00	547+00.00	16,605.00		1845.00	
N.B.	547+00.00	552+15.43	5,647.00		627.44	
N.B.	552+54.93	573+00.00	21,388.00		2376.44	

CLASS D PATCHES, TYPE I, 10 INCH					TOTAL 1131	SQ YD
STATION	LENGTH (FT)	ADJ. LENGTH (FT)	WIDTH (FT)		SUBTOTALS (SQ YD)	
S.B. LANE 1						
585+68.23	4.00	4.80	7.00		3.73	
582+75.54	7.00	8.40	5.00		2.67	
580+75.25	7.00	8.40	5.00		4.67	
578+75.57	7.00	8.40	5.00		4.67	
	3.00	3.60	7.00		2.80	
577+77.15	3.00	3.60	5.00		2.00	
575+75.66	4.00	4.80	7.00		3.73	
	4.00	4.80	5.00		2.67	
573+76.18	4.00	4.80	7.00		3.73	
	4.00	4.80	5.00		2.67	
571+29.24	7.00	8.40	5.00		4.67	
	4.00	4.80	7.00		3.73	
569+76.44	4.00	4.80	5.00		2.67	
568+79.58	5.00	6.00	7.00		4.67	
568+76.82	5.00	6.00	5.00		3.33	
567+83.93	4.00	4.80	7.00		3.73	
567+75.20	4.00	4.80	5.00		2.67	
566+71.39	4.00	4.80	7.00		3.73	
565+80.93	4.00	4.80	5.00		2.67	
564+84.66	4.00	4.80	7.00		3.73	
	4.00	4.80	5.00		2.67	
	4.00	4.80	7.00		3.73	
563+79.47	4.00	4.80	5.00		2.67	
	4.00	4.80	7.00		3.73	
560+77.18	4.00	4.80	5.00		2.67	
558+74.17	7.00	8.40	5.00		4.67	
	4.00	4.80	7.00		3.73	
557+77.21	4.00	4.80	5.00		2.67	
	4.00	4.80	7.00		3.73	
556+68.97	4.00	4.80	5.00		2.67	
	5.00	6.00	7.00		4.67	
554+75.27	5.00	6.00	5.00		3.33	
	4.00	4.80	7.00		3.73	
554+24.04	4.00	4.80	5.00		2.67	
553+77.45	4.00	4.80	7.00		3.73	
552+79.44	4.00	4.80	5.00		2.67	
551+74.37	7.00	8.40	5.00		4.67	
554+80.52	5.00	6.00	7.00		4.67	
544+76.02	5.00	6.00	5.00		3.33	
542+80.14	4.00	4.80	7.00		3.73	
	4.00	4.80	5.00		2.67	
540+77.43	7.00	8.40	5.00		4.67	

CONTINUED IN THE NEXT COLUMN

CONTINUED FROM PREVIOUS COLUMN

STATION	LENGTH (FT)	ADJ. LENGTH (FT)	WIDTH (FT)	TYPE II (SQ YD)	Sub totals (SQ YD)
538+76.39	7.00	8.40	5.00		4.67
535+80.52	4.00	4.80	7.00		3.73
	4.00	4.80	5.00		2.67
534+81.68	4.00	4.80	7.00		3.73
	4.00	4.80	5.00		2.67
530+81.14	4.00	4.80	7.00		3.73
530+76.02	4.00	4.80	5.00		2.67
529+77.61	6.00	7.20	5.00		4.00
527+77.23	7.00	8.40	5.00		4.67
526+80.66	4.00	4.80	7.00		3.73
526+75.54	4.00	4.80	5.00		2.67
522+04.30	4.00	4.80	7.00		3.73
521+99.24	4.00	4.80	5.00		2.67
520+76.18	8.00	9.60	4.00		4.27
516+76.02	6.00	7.20	4.00		3.20
	5.00	6.00	7.00		4.67
507+76.35	5.00	6.00	5.00		3.33
	4.00	4.80	7.00		3.73
503+81.99	4.00	4.80	5.00		2.67
493+76.66	6.00	7.20	5.00		4.00
492+79.05	4.00	4.80	7.00		3.73
492+66.14	4.00	4.80	5.00		2.67
489+77.35	7.00	8.40	5.00		4.67
487+75.85	4.00	4.80	7.00		3.73
486+83.25	4.00	4.80	5.00		2.67
482+76.63	6.00	7.20	5.00		4.00
476+81.07	4.00	4.80	7.00		3.73
	4.00	4.80	5.00		2.67
476+52.57	4.00	4.80	7.00		3.73
475+83.80	4.00	4.80	5.00		2.67
474+77.59	7.00	8.40	5.00		4.67
	4.00	4.80	7.00		3.73
464+12.50	4.00	4.80	5.00		2.67
463+74.19	4.00	4.80	7.00		3.73
462+88.17	4.00	4.80	5.00		2.67
	4.00	4.80	7.00		3.73
459+76.75	4.00	4.80	5.00		2.67
457+82.02	4.00	4.80	7.00		3.73
457+77.60	4.00	4.80	5.00		2.67
454+64.43	6.00	7.20	5.00		4.00
444+57.61	4.00	4.80	7.00		3.73
444+32.54	4.00	4.80	5.00		2.67
443+62.72	4.00	4.80			