

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) WRS-2	WILL	228	24
STA.		TO STA.		
FED. DIST. NO.	ILLINOIS	FED. AID PROJECT		

FROM STATION	TO STATION	EARTH EXCAVATION CU YD	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL CU YD	EXCAVATION TO BE USED IN (15% SHRINKAGE) EMBANKMENT CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD	TOPSOIL EXCAVATION AND PLACEMENT CU YD	PGE, SUBGRADE CU YD
BASINS (PRE-STAGE)								
471+00.00	LT	265.0	116.0	225.3	1.3	223.9	0.0	0.0
PERMANENT DITCH CHECKS (PRE-STAGE)								
477+10.00	481+00.00	0.0	110.0	0.0	7.8	-7.8	0.0	0.0
PRE-STAGE TOTAL		265.0	226.0	225.3	9.1	216.1	0.0	0.0

FROM STATION	TO STATION	EARTH EXCAVATION CU YD	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL CU YD	EXCAVATION TO BE USED IN (15% SHRINKAGE) EMBANKMENT CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD	TOPSOIL EXCAVATION AND PLACEMENT CU YD	PGE, SUBGRADE CU YD
402+65.07	403+00.00	50.2	50.2	42.7	2.1	40.5	0.0	0.0
403+00.00	404+00.00	114.1	114.1	97.0	12.7	84.3	0.0	0.0
404+00.00	405+00.00	78.6	78.6	66.9	29.5	37.4	0.0	0.0
405+00.00	406+00.00	76.3	76.3	64.9	39.9	25.0	0.0	0.0
406+00.00	407+00.00	80.6	80.6	68.5	37.1	31.3	0.0	0.0
407+00.00	408+00.00	82.7	82.7	70.3	26.5	43.8	0.0	0.0
408+00.00	409+00.00	78.6	78.6	66.8	31.3	35.5	0.0	0.0
409+00.00	410+00.00	72.2	72.2	61.3	52.2	9.1	0.0	0.0
410+00.00	411+00.00	71.4	71.4	60.7	65.4	-4.7	0.0	0.0
411+00.00	412+00.00	69.6	69.6	59.1	75.7	-16.6	0.0	0.0
412+00.00	413+00.00	64.9	64.9	55.1	83.6	-28.4	0.0	0.0
413+00.00	414+00.00	64.1	64.1	54.4	82.9	-28.5	0.0	0.0
414+00.00	415+00.00	66.4	66.4	56.4	80.0	-23.5	0.0	0.0
415+00.00	416+00.00	68.8	68.8	58.5	78.0	-19.5	0.0	0.0
416+00.00	417+00.00	67.4	67.4	57.3	75.5	-18.2	0.0	0.0
417+00.00	418+00.00	69.7	69.7	59.3	65.3	-6.0	0.0	0.0
418+00.00	419+00.00	76.9	76.9	65.4	48.6	16.8	0.0	0.0
419+00.00	420+00.00	79.1	79.1	67.2	42.5	24.7	0.0	0.0
420+00.00	421+00.00	78.8	78.8	67.0	44.4	22.6	0.0	0.0
421+00.00	422+00.00	78.6	78.6	66.8	46.1	20.7	0.0	0.0
422+00.00	423+00.00	78.9	78.9	67.1	46.4	20.6	0.0	0.0
423+00.00	424+00.00	80.4	80.4	68.3	42.6	25.7	0.0	0.0
424+00.00	425+00.00	82.6	82.6	70.2	37.1	33.0	0.0	0.0
425+00.00	426+00.00	84.3	84.3	71.7	17.4	54.3	0.0	36.6
426+00.00	427+00.00	82.9	82.9	70.5	0.0	70.5	0.0	88.2
427+00.00	428+00.00	80.1	80.1	68.1	0.0	68.1	0.0	112.7
428+00.00	429+00.00	80.3	80.3	68.3	23.3	45.0	0.0	61.0
429+00.00	430+00.00	82.8	82.8	70.4	42.0	28.4	0.0	0.0
430+00.00	431+00.00	85.3	85.3	72.5	35.0	37.5	0.0	0.0
431+00.00	432+00.00	87.0	87.0	74.0	32.9	41.1	0.0	0.0
432+00.00	433+00.00	88.4	88.4	75.1	33.2	41.9	0.0	0.0
433+00.00	434+00.00	86.1	86.1	73.1	35.8	37.4	0.0	0.0
434+00.00	435+00.00	81.3	81.3	69.1	42.7	26.4	0.0	0.0
435+00.00	436+00.00	78.0	78.0	66.3	51.7	14.6	0.0	0.0
436+00.00	437+00.00	76.7	76.7	65.2	55.4	9.8	0.0	0.0
437+00.00	438+00.00	77.9	77.9	66.2	51.8	14.4	0.0	0.0
438+00.00	439+00.00	79.7	79.7	67.7	46.4	21.3	0.0	0.0
439+00.00	440+00.00	79.9	79.9	67.9	45.4	22.5	0.0	0.0
440+00.00	441+00.00	78.2	78.2	66.5	49.6	16.9	0.0	0.0
441+00.00	442+00.00	76.5	76.5	65.0	54.6	10.5	0.0	0.0
442+00.00	443+00.00	75.5	75.5	64.2	57.8	6.4	0.0	0.0
443+00.00	444+00.00	75.6	75.6	64.3	57.7	6.5	0.0	0.0
444+00.00	445+00.00	76.2	76.2	64.8	56.2	8.6	0.0	0.0
445+00.00	446+00.00	76.8	76.8	65.2	54.4	10.8	0.0	0.0
446+00.00	447+00.00	77.1	77.1	65.6	52.1	13.5	0.0	0.0
447+00.00	448+00.00	77.5	77.5	65.9	49.4	16.4	0.0	0.0
448+00.00	449+00.00	77.9	77.9	66.2	48.0	18.2	0.0	0.0
449+00.00	450+00.00	78.3	78.3	66.6	23.9	42.6	0.0	57.0
450+00.00	451+00.00	76.7	76.7	65.2	0.0	65.2	0.0	118.5
451+00.00	452+00.00	75.3	75.3	64.0	0.0	64.0	0.0	122.2
452+00.00	453+00.00	77.1	77.1	65.5	0.0	65.5	0.0	118.6
453+00.00	454+00.00	79.5	79.5	67.6	0.0	67.6	0.0	112.8
454+00.00	455+00.00	79.3	79.3	67.4	0.0	67.4	0.0	111.1
455+00.00	456+00.00	77.7	77.7	66.1	0.0	66.1	0.0	112.1
456+00.00	457+00.00	77.7	77.7	66.0	0.0	66.0	0.0	110.8
457+00.00	458+00.00	77.3	77.3	65.7	0.0	65.7	0.0	113.5
458+00.00	459+00.00	76.1	76.1	64.6	28.7	36.0	0.0	58.6
459+00.00	460+00.00	75.0	75.0	63.8	59.0	4.7	0.0	0.0
460+00.00	461+00.00	73.8	73.8	62.8	62.5	0.3	0.0	0.0
461+00.00	462+00.00	72.4	72.4	61.5	65.9	-4.4	0.0	0.0
462+00.00	463+00.00	71.0	71.0	60.3	69.3	-9.0	0.0	0.0
463+00.00	464+00.00	69.9	69.9	59.4	70.3	-10.9	0.0	0.0
464+00.00	465+00.00	69.3	69.3	58.9	68.2	-9.4	0.0	0.0
465+00.00	466+00.00	68.8	68.8	58.5	65.0	-6.6	0.0	0.0
466+00.00	467+00.00	71.8	71.8	61.0	59.0	2.0	0.0	0.0
467+00.00	468+00.00	75.9	75.9	64.5	51.8	12.7	0.0	0.0
468+00.00	469+00.00	78.1	78.1	66.4	45.9	20.5	0.0	0.0
469+00.00	470+00.00	79.8	79.8	67.8	40.2	27.6	0.0	0.0
470+00.00	471+00.00	77.4	77.4	65.8	38.1	27.6	0.0	0.0
471+00.00	472+00.00	147.9	147.9	125.7	19.4	106.3	0.0	0.0
472+00.00	473+00.00	222.3	222.3	188.9	0.0	188.9	0.0	0.0
473+00.00	474+00.00	205.8	205.8	174.9	0.0	174.9	0.0	0.0
474+00.00	475+00.00	205.6	205.6	174.8	0.0	174.8	0.0	0.0
475+00.00	476+00.00	221.9	221.9	188.6	0.0	188.6	0.0	0.0
476+00.00	477+00.00	146.4	146.4	124.5	35.7	88.8	0.0	0.0
477+00.00	478+00.00	72.6	72.6	61.8	70.1	-8.4	0.0	0.0

FROM STATION	TO STATION	EARTH EXCAVATION CU YD	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL CU YD	EXCAVATION TO BE USED IN (15% SHRINKAGE) EMBANKMENT CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD	TOPSOIL EXCAVATION AND PLACEMENT CU YD	PGE, SUBGRADE CU YD
478+00.00	479+00.00	73.4	77.8	62.4	67.6	-5.2	0.0	0.0
479+00.00	480+00.00	74.1	77.8	63.0	64.2	-1.2	0.0	0.0
480+00.00	481+00.00	75.7	77.8	64.3	54.9	9.5	0.0	0.0
481+00.00	482+00.00	78.4	77.8	66.7	40.8	25.8	0.0	0.0
482+00.00	483+00.00	81.3	77.8	69.1	30.0	39.1	0.0	0.0
483+00.00	484+00.00	82.4	77.8	70.1	27.1	43.0	0.0	0.0
484+00.00	485+00.00	82.3	77.8	70.0	29.0	41.0	0.0	0.0
485+00.00	486+00.00	81.9	77.8	69.6	31.8	37.8	0.0	0.0
486+00.00	487+00.00	81.4	77.8	69.2	36.4	32.8	0.0	0.0
487+00.00	488+00.00	81.2	77.8	69.1	41.8	27.3	0.0	0.0
488+00.00	489+00.00	134.0	77.8	113.9	22.2	91.6	0.0	0.0
489+00.00	490+00.00	180.8	77.7	153.7	0.0	153.7	0.0	0.0
490+00.00	491+00.00	173.9	77.7	147.8	0.0	147.8	0.0	0.0
491+00.00	491+42.75	36.9	16.6	31.4	0.0	31.4	0.0	0.0
491+42.75	492+49.25	0.0	0.0	0.0	0.0	0.0	0.0	0.0
492+49.25	493+00.00	49.2	19.7	41.8	0.0	41.8	0.0	0.0
493+00.00	494+00.00	218.5	77.8	185.8	0.0	185.8	0.0	0.0
494+00.00	495+00.00	217.2	77.8	184.6	0.0	184.6	0.0	0.0
495+00.00	496+00.00	211.2	77.8	179.6	0.0	179.6	0.0	0.0
496+00.00	497+00.00	170.1	77.8	144.6	1.7	142.9	0.0	0.0
497+00.00	498+00.00	110.7	77.8	94.1	2.4	91.7	0.0	0.0
498+00.00	499+00.00	113.2	77.8	96.2	1.5	94.7	0.0	0.0
499+00.00	500+00.00	109.7	77.8	93.2	3.3	90.0	0.0	0.0
500+00.00	501+00.00	103.2	77.8	87.8	6.7	81.0	0.0	0.0
501+00.00	502+00.00	97.0	77.8	82.5	11.4	71.1	0.0	0.0
502+00.00	503+00.00	88.0	77.7	74.8	23.3	51.5	0.0	0.0
503+00.00	504+00.00	78.1	77.7	66.4	44.3	22.1	0.0	0.0
504+00.00	505+00.00	70.4	77.8	59.8	61.9	-2.0	0.0	0.0
505+00.00	506+00.00	71.2	77.8	60.5	61.5	-1.0	0.0	0.0
506+00.00	507+00.00	194.3	38.9	165.2	27.8	137.3	0.0	0.0
507+00.00	508+00.00	314.0	0.0	266.9	0.0	266.9	0.0	0.0
508+00.00	509+00.00	290.4	0.0	246.8	0.0	246.8	0.0	0.0
509+00.00	510+00.00	170.2	38.9	144.6	27.7	117.0	0.0	0.0
510+00.00	511+00.00	75.4	77.8	64.1	52.2	11.9	0.0	0.0
511+00.00	512+00.00	76.8	77.8	65.3	47.8	17.5	0.0	0.0
512+00.00	513+00.00	77.3	77.8	65.7	45.7	20.0	0.0	0.0
513+00.00	514+00.00	77.6	77.8	65.9	43.5	22.4	0.0	0.0
514+00.00	515+00.00	77.5	77.8	65.8	41.1	24.7	0.0	0.0
515+00.00	516+00.00	77.8	77.8	66.2	38.9	27.3	0.0	0.0
516+00.00	517+00.00	78.0	77.8	66.3	39.5	26.8	0.0	0.0
517+00.00	518+00.00	76.4	77.8	64.9	44.3	20.6	0.0	0.0
518+00.00	519+00.00	73.5	77.8	62.5	50.8	11.6	0.0	0.0
519+00.00	520+00.00	73.9						