CONTRACT NO. 60B46

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 55 | 99 (1&2) WRS-2 | WILL | 228 | 25 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

CONTINUED FROM SHEET 24

| FROM STATION | TO STATION | EARTH EXCAVATION CU YD | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL CU YD | EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) CU YD | EMBANKMENT CU YD | EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD | TOPSOIL EXCAVATION AND PLACEMENT CU YD | PCC, SUBGRADE CU YD |
|---|---|---|---|---|---|---|---|---|
| I-55 MAINLINE (STAGE I) | | | | | | | | |
| 559+00.00 | 560+00.00 | 85.4 | 77.8 | 72.6 | 38.6 | 34.0 | 0.0 | 0.0 |
| 560+00.00 | 561+00.00 | 87.3 | 77.8 | 74.2 | 35.6 | 38.5 | 0.0 | 0.0 |
| 561+00.00 | 562+00.00 | 89.5 | 77.8 | 76.1 | 28.9 | 47.2 | 0.0 | 0.0 |
| 562+00.00 | 563+00.00 | 92.5 | 77.8 | 78.6 | 22.5 | 56.1 | 0.0 | 0.0 |
| 563+00.00 | 564+00.00 | 94.6 | 77.8 | 80.4 | 18.6 | 61.7 | 0.0 | 0.0 |
| 564+00.00 | 565+00.00 | 94.6 | 77.8 | 80.4 | 19.4 | 61.0 | 0.0 | 0.0 |
| 565+00.00 | 566+00.00 | 93.6 | 77.8 | 79.6 | 22.3 | 57.3 | 0.0 | 0.0 |
| 566+00.00 | 567+00.00 | 92.2 | 77.8 | 78.4 | 25.5 | 52.9 | 0.0 | 0.0 |
| 567+00.00 | 568+00.00 | 90.0 | 77.8 | 76.5 | 29.8 | 46.7 | 0.0 | 0.0 |
| 568+00.00 | 569+00.00 | 88.0 | 77.8 | 74.8 | 35.0 | 39.8 | 0.0 | 0.0 |
| 569+00.00 | 570+00.00 | 86.8 | 77.8 | 73.8 | 40.1 | 33.7 | 0.0 | 0.0 |
| 570+00.00 | 571+00.00 | 85.1 | 77.8 | 72.3 | 44.7 | 27.6 | 0.0 | 0.0 |
| 571+00.00 | 572+00.00 | 83.4 | 77.8 | 70.8 | 44.9 | 26.0 | 0.0 | 0.0 |
| 572+00.00 | 573+00.00 | 41.4 | 38.9 | 35.2 | 21.5 | 13.7 | 0.0 | 0.0 |
| 573+00.00 | END | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| STAGE I TOTALS | | 15627.8 | 13652.2 | 13283.7 | 6399.3 | 6884.4 | 0.0 | 1610.1 |
| **TOTALS** | | 15892.8 | 13878.2 | 13508.9 | 6408.4 | 7100.5 | 0.0 | 1610.1 |

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $$CALE$
USER NAME = $USER$

S:\DEL4003\IDOT\..\B99WARREN\D2N
3-22-2007,13:39:45 GARCIAWZ
S:\DOCUMENT\B2361501\CIVIL\DGN\SC2B04A22.SHT

REVISIONS

| NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (BLACK ROAD TO U.S. 30)
WIDENING AND RESURFACING

## SCHEDULE OF QUANTITIES XVIII

SCALE: N.T.S. DRAWN BY KV
DATE 03/22/07 CHECKED BY DDH

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS