CONTRACT NO. 60B46

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 55 | 99 (1&2) WRS-2 | WILL | 228 | 157 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

# SCHEDULE OF QUANTITIES - SIGNING

| | | | SIGN PANEL, TY 3 AND STRUCTURES | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | SIGN NO. | | 1G099I055R255.4 | | 1G099I055R256.7 | | SIGN PANEL | SIGN PANEL | SIGN PANEL | SIGN PANEL | SIGN PANEL | MILEPOST | SIGN PANEL |
| | STATION | | 475+45 | MP 255.37 | 545+30 | MP 256.7 | ASSEMBLY | | ASSEMBLY | | ASSEMBLY | MARKER | ASSEMBLY |
| | SIZE (WIDTHxHEIGHT) | | 20'x10' | | 10'-6"x7' | | TYPE 3 | TYPE 3 | TYPE 2 | TYPE 2 | TYPE B | ASSEMBLY | TYPE A |
| PAY ITEM | TOTAL QUANTITY | UNIT | INSTALLATION | REMOVAL | INSTALLATION | REMOVAL | INSTALLATION | REMOVAL | INSTALLATION | REMOVAL | REMOVAL | INSTALLATION | REMOVAL |
| REINFORCEMENT BARS | 360 | POUND | 200 | | 160 | | | | | | | | |
| SIGN PANEL - TYPE 2 | 169 | SQ FT | | | | | | | 169 | | | | |
| SIGN PANEL - TYPE 3 | 2133 | SQ FT | 200 | | 73.5 | | 1859.5 | | | | | | |
| REMOVE SIGN PANEL ASSEMBLY - TYPE A | 9 | EACH | | | | | | | | | | | 9 |
| REMOVE SIGN PANEL ASSEMBLY - TYPE B | 11 | EACH | | | | | | | | | 11 | | |
| REMOVE SIGN PANEL - TYPE 2 | 20 | SQ FT | | | | | | | | 20 | | | |
| REMOVE SIGN PANEL - TYPE 3 | 2018 | SQ FT | | 200 | | 70 | | 1748 | | | | | |
| MILE POST MARKER ASSEMBLY | 7 | EACH | | | | | | | | | | 7 | |
| STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY | 1546 | POUND | 1235 | 310.5 | | | | | | | | | |
| WOOD SIGN SUPPORT | 300 | FOOT | | | | | 120 | | 180 | | | | |
| CONCRETE FOUNDATIONS | 3.9 | CU YD | 2.54 | | 1.4 | | | | | | | | |
| REMOVE GROUND-MOUNTED SIGN SUPPORT | 5 | EACH | | 2 | | 3 | | | | | | | |
| REMOVE CONCRETE FOUNDATION - GROUND MOUNT | 5 | EACH | | 2 | | 3 | | | | | | | |

| REVISIONS | |
|---|---|
| NAME | DATE |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (BLACK ROAD TO U.S. 30)
WIDENING AND RESURFACING

**SCHEDULE OF QUANTITES**
**SIGNING**

SCALE: N.T.S. DRAWN BY AG
DATE 02/23/07 CHECKED BY DH

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
USER NAME = $USER$
..\B99WA001.DGN
2-28-2007,19:00:11
GARCIAAZ
S:\DOCUMENTS\B23G5B\CIVIL\DGNS\CP01A100.SHT