

# SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59	*	WILL	102	4
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
* 99(1&2)AC-R-2		CONTRACT NO. 60B97		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	WILL COUNTY									
				ROADWAY WESTERN FRONTAGE ROAD	SIGNING	STRUCTURE CULVERT	CONSTRUCTION TYPE CODE						
				1000-2A	Y002-1C	Y007							
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	56	56									
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	71	71									
20101100	TREE TRUNK PROTECTION	EACH	4	4									
20200100	EARTH EXCAVATION	CU YD	7,235	7,235									
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	8554	8554									
20400800	FURNISHED EXCAVATION	CU YD	13,430	13,430									
20700220	POROUS GRANULAR EMBANKMENT	CU YD	23			23							
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	189	189									
20800150	TRENCH BACKFILL	CU YD	200	200									
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	3,244	3,244									
25000210	SEEDING, CLASS 2A	ACRE	6.00	6.00									
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	523	523									
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	523	523									
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	523	523									
25100630	EROSION CONTROL BLANKET	SQ YD	62,080	62,080									
25200110	SODDING, SALT TOLERANT	SQ YD	1,060	1,060									
25200200	SUPPLEMENTAL WATERING	UNIT	31.8	31.8									
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	25	25									
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	701	701									
28000300	TEMPORARY DITCH CHECKS	EACH	30	30									
28000400	PERIMETER EROSION BARRIER	FOOT	5,923	5,923									
28000500	INLET AND PIPE PROTECTION	EACH	6	6									
28000510	INLET FILTERS	EACH	16	16									
28001000	AGGREGATE (EROSION CONTROL)	TON	5	5									
28100107	STONE RIPRAP, CLASS A4	SQ YD	70	70									
40300100	<del>BITUMINOUS MATERIALS (PRIME COAT)</del>	<del>GALLON</del>	<del>292</del>	<del>292</del>									
28200100	<del>FILTER FABRIC</del>	<del>SQ YD</del>	<del>70</del>	<del>70</del>									
40600300	<del>AGGREGATE (PRIME COAT)</del>	<del>TON</del>	<del>6</del>	<del>6</del>									
31101906	<del>SUB-BASE GRANULAR MATERIAL, TYPE C</del>	<del>TON</del>	<del>1,935</del>	<del>1,935</del>									
31102500	<del>SUB-BASE GRANULAR MATERIAL, TYPE C B"</del>	<del>SQ YD</del>	<del>4,488</del>	<del>4,488</del>									
35102000	<del>AGGREGATE BASE COURSE, TYPE B 8"</del>	<del>SQ YD</del>	<del>200</del>	<del>200</del>									
44201753	<del>CLASS D PATCHES, TYPE II, 9 INCH</del>	<del>SQ YD</del>	<del>175</del>	<del>175</del>									
40300100	<del>BITUMINOUS MATERIALS (PRIME COAT)</del>	<del>GALLON</del>	<del>1,285</del>	<del>1,285</del>									
44201757	<del>CLASS D PATCHES, TYPE III, 9 INCH</del>	<del>SQ YD</del>	<del>117</del>	<del>117</del>									
40600895	<del>CONSTRUCTING TEST STRIP</del>	<del>EACH</del>	<del>2</del>	<del>2</del>									
40600635	<del>LEVELING BINDER (MACHINE METHOD)</del>	<del>TON</del>	<del>123</del>	<del>123</del>									
40603340	<del>HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70</del>	<del>TON</del>	<del>292</del>	<del>292</del>									
48102100	<del>AGGREGATE WEDGE SHOULDER</del>	<del>TON</del>	<del>51</del>	<del>51</del>									
40701996	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 15 3/4"	SQ YD	12,852.0	12,852.0									

\* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAI 55 WEST FRONTAGE ROAD AT IL 59  
SECTION: 99(1&2)AC-R-2

## SUMMARY OF QUANTITIES I

SCALE: \_\_\_\_\_ DRAWN BY: JB  
DATE: 03/22/2007 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.  
ENGINEERS/ARCHITECTS/PLANNERS  
265 N. MICHIGAN AVE. CHICAGO, IL 60601  
TELEPHONE: 312.644.6000

Rev. 5-30-07 Rev.

S:\00029404\1\SU00029404\1\TERR0267.DWG  
 7-22-2007 8:59:01  
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63