

## SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	WILL COUNTY									
				ROADWAY WESTERN FRONTAGE ROAD	SIGNING	STRUCTURE CULVERT	CONSTRUCTION TYPE CODE						
				I000-2A	Y002-10	Y007							
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	22										
<del>42001300</del>	<del>PROTECTIVE COAT</del>	<del>SQ YD</del>	<del>122</del>	<del>122</del>									
44000100	PAVEMENT REMOVAL	SQ YD	8,736	8,736									
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	658	658									
<del>44004850</del>	<del>PAVED SHOULDER REMOVAL</del>	<del>SQ YD</del>	<del>870</del>	<del>870</del>									
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	918	918									
<del>48101500</del>	<del>AGGREGATE SHOULDERS, TYPE B 6"</del>	<del>SQ YD</del>	<del>447</del>	<del>447</del>									
48203009	HOT-MIX ASPHALT SHOULDERS, 3"	SQ YD	141	141									
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	3,759	3,759									
50104300	CONCRETE HEADWALL REMOVAL	CU YD	1	1									
50105220	PIPE CULVERT REMOVAL	FOOT	44	44									
51205200	TEMPORARY SHEET PILING	SQ FT	850			850							
54000900	BOX CULVERT END SECTIONS, SPECIAL	EACH	2			2							
54020302	PRECAST CONCRETE BOX CULVERT 3' X 2' (M273)	FOOT	74.5			74.5							
54200433	PIPE CULVERTS, TYPE 1 RCCP 18"	FOOT	46	46									
54202137	PIPE CULVERTS, TYPE 3 RCCP 42"	FOOT	75	75									
<del>54205062</del>	<del>PIPE CULVERTS, SPECIAL 21"</del>	<del>FOOT</del>	<del>51</del>	<del>51</del>									
54207153	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	FOOT	193	193									
54207156	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 21"	FOOT	42	42									
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2									
54214713	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	EACH	4	4									
54214716	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 21"	EACH	2	2									
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	534	534									
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	8	8									
55100900	STORM SEWER REMOVAL 18"	FOOT	518	518									
55101800	STORM SEWER REMOVAL 42"	FOOT	46	46									
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE B GRATE	EACH	3	3									
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1									
60206805	CATCH BASINS, TYPE B, SPECIAL	EACH	1	1									
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1									
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1									
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1									
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1	1									
60500040	REMOVING MANHOLES	EACH	1	1									
60500050	REMOVING CATCH BASINS	EACH	2	2									

\* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAI 55 WEST FRONTAGE ROAD AT IL 59  
SECTION: 99(1&2)AC-R-2

### SUMMARY OF QUANTITIES II

SCALE: DRAWN BY: JB  
DATE: 03/22/2007 CHECKED BY: ACL

## TENG

TENG & ASSOCIATES, INC.  
ENGINEERS/ARCHITECTS/PLANNERS  
205 N. WASHINGTON AVE. CHICAGO, IL 60601  
TELEPHONE: 312-892-0800

\\S:\000078\DCN... \S\000078\DCN... \T\000078\DCN... 1-22-2007 8:58:24 AM T:\DOCUMENT\19227800\CIVIL\DCN\S\000078\DCN... 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63