

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	3034 RS-3	COOK	24	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN 100%STATE 1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	21	21					
40600300	AGGREGATE (PRIME COAT)	TON	80	80					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	21	21					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4300	4300					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	350	350					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	38118	38118					
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	6.78	6.78					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2475	2475					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	240	240					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1900	1900					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5					
60250300	CATCH BASINS TO BE ADJUSTED (SPECIAL)	EACH	22	22					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4000	4000					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	437	437					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	18592	18592					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1865	1865					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2000	2000					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	330	330					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1200	1200					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN 100%STATE 1000					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	437	437					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18592	18592					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1865	1865					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2000	2000					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	330	330					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	340	340					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	326	326					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	716	716					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	232	232					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1812	1812					
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	7210	7210					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	85	85					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					

4/13/2007 8:52:26 AM C:\PROJECTS\60C71\60C71.DWG

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

\*SPECIALTY ITEMS RCV.