

CONTRACT NO. 60004

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	2007-028 RS	COOK	23	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000	TRAFFIC SIGNALS YO31-1F	SFTY-2A 016-0535		
20201006	GRADING AND SHAPING SHOULDERS	UNIT	106	106				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24	24				
40600300	AGGREGATE (PRIME COAT)	TON	116	116				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9	9				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	210	210				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	395	395				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2825	2825				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	28800	28800				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	85	85				
44002220	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5"	SQ YD	1392	1392				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1200	1200				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	112	112				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	80	80				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1150	1150				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	31	31				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	0.8	0.1	0.1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2000	2000				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	454.3	454.3				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	26200	26200				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2000	2000				

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000	TRAFFIC SIGNALS YO31-1F	SFTY-2A 016-0535		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	480	480				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	450	450				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	454.3	454.3				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	26200	26200				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2000	2000				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	480	480				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	450	450				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	290	290				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	290	290				
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3		3			
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2195		2195			
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	6		6			
* 88600100	DETECTOR LOOP, TYPE I	FOOT	310		310			
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	660		660			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	302.5	302.5				
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	150			150		
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1215	1215				

4/12/2007 10:00:00 AM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

*SPECIALTY ITEMS

PLOT DATE: 4/12/2007