CONTRACT NO. 60D04 | F.A.P | SECTION | COUNTY | TOTAL | SHEETS | NO. | 305 | 2007-028 R\$ | COOK | 23 | 22 STA. TO STA. FED. ROAD DIST. NO. | ILLINDIS | FED. AID PROJECT 68 (1700) 54 (1350) (175) (175) ROAD WORK (1125) 45 EXPECT DELAYS USE APPROPRIATE MONTH AND DATE FOR CONTRACT —1 (25) BLACK BORDER m) MIN. # BEGINS XXX XX 58 (1450) /\_ NOTES: 1. USE BLACK LETTERING ON ORANGE BACKGROUND. 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER. 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION. 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION. 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION. 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.) 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING. ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN. ILLINOIS DEPARTMENT OF TRANSPORTATION ARTERIAL ROAD T. RAMMACHER INFORMATION SIGN SCALE: NONE DRAWN BY DESIGN

CHECKED BY