

CONTRACT NO. 60D05

F.A. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	*	COOK	32	3
STA. TO STA.		ILLINOIS FED. AID PROJECT		

* 2007-029-RS
** FAP 330, FAU 1362

SUMMARY OF QUANTITIES

ENGLISH	PAY ITEM DESCRIPTION	UNIT	FAP 330 FAU 1362		
			URBAN TOTAL QUANTITY 100% STATE	1000 MANNHEIM ROAD	1000 LAWRENCE AVENUE
20200600	EXCAVATING AND GRADING EXISTING SHOULDERS	UNIT	534	534	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	149	138	11
40600300	AGGREGATE (PRIME COAT)	TON	679	624	55
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	68	62	6
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	11,921	10,577	1,344
40600895	CONSTRUCTING TEST STRIP	EACH	4	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	825	608	217
40600990	TEMPORARY RAMP	SQ YD	558	414	144
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1,660	1,270	390
42001300	PROTECTIVE COAT	SQ YD	527	342	185
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	121,639	107,927	13,712
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,835	1,025	810
44002206	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 1 1/2"	SQ YD	4,660		4,660
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	6,500	6,500	
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	75		75
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	20		20
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	3,990		3,990
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	3,900	3,900	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	360	360	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1,438	1,438	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"	SQ YD	48,041	48,041	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	748	748	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	4,035	4,035	
55039700	STORM SEWERS TO BE CLEANED	FOOT	800		800
60250200	CATCH BASINS TO BE ADJUSTED	EACH	9	0	9
60251900	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	38	38	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	4	0	4
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	16		16
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	51	26	25
60404940	FRAMES AND GRATE, TYPE 23	EACH	8		8
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	10		10
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	4		4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	5	5	
63200310	GUARDRAIL REMOVAL	FOOT	225	225	
67000200	ENGINEER'S FIELD OFFICE, TYPE A	EACH	4	3	1
67100100	MOBILIZATION	L SUM	1	0.8	0.2
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	EACH	1	1	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2330	2038	292
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1		1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	23,858	22,408	1,450
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,165	1,019	146
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	68,997	62,540	6,457
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5,664	5,264	400
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	11,179	11,179	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,360	2,360	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	482	394	88
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,372	1,372	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	5	5	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,372	1,372	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2,567	1,782	785
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	154	103	51
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5,109	4,533	576
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	47		47
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	137,944	125,080	12,914
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	11,328	10,528	800
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	22,358	21,358	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	4,720	4,720	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	41,964	36,4	176

* SPECIALTY ITEMS

REVISIONS	ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	SUMMARY OF QUANTITIES
DATE	FAP 330 (US 12/45) FAU 1362 (LAWRENCE AVENUE)
	SCALE: DRAWN BY: DATE: CHECKED BY:
	GRAEF, ANHALT, SCHLOEMER & ASSOCIATES, INC. CHICAGO, ILLINOIS