

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY	SIGNAL	INTERCONNECT	PREEMPTORS	LIGHTING	CODE NO	ITEM	UNIT		ROADWAY	SIGNAL	INTERCONNECT	PREEMPTORS	LIGHTING
				1000-2A	Y031-1F	Y031-1F	Y031-3D	Y030-1E					1000-2A	Y031-1F	Y031-1F	Y031-3D	Y030-1E
			90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% COUNTY	100% STATE	100% VILLAGE OF HUNTLEY	90% FEDERAL 10% STATE				90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% COUNTY	100% STATE	100% VILLAGE OF HUNTLEY	90% FEDERAL 10% STATE		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	18900	18900					81400300	DOUBLE HANDHOLE	EACH	1					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1600	1600					81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	7509		809	4200	2500	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	200	200					83050800	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 12 FT. MAST ARM	EACH	13				13	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	210	210					83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	130				130	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8200	8200					83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	13				13	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	33						85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1		1			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150	150					85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9450	9450					86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	800	800					<del>87301225</del>	<del>ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 30</del>	<del>FOOT</del>	<del>409</del>		<del>409</del>			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100					87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1411		1411			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	105	105					87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1893		1893			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	110	110					87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1823		1823			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	100	100					87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	53		53			
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1						<del>87502520</del>	<del>TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.</del>	<del>EACH</del>	<del>1</del>		<del>1</del>			
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1						87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1		1			
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	4759		559	4200			87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1			
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	131		131				87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	1		1			
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	21		21				87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	1		1			
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	103		103				87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1		1			
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	44		44				87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1		1			
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	277		277				<del>87800100</del>	<del>CONCRETE FOUNDATION, TYPE A</del>	<del>FOOT</del>	<del>4</del>		<del>4</del>			
81400200	HEAVY-DUTY HANDHOLE	EACH	16		9	7			87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4			

\* SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	SUMMARY OF QUANTITIES	

Rev.

PLOT DATE: 2/13/2007

Rev.

2/13/2007 11:38:38 AM