

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT		ROADWAY	SIGNAL	INTERCONNECT	PREEMPTORS	LIGHTING	CODE NO	ITEM	UNIT		ROADWAY	SIGNAL	INTERCONNECT	PREEMPTORS	LIGHTING			
				1000-2A	YO31-1F	YO31-1F	YO31-3D	YO30-1E					90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% COUNTY	100% STATE	100% VILLAGE OF HUNTLEY	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	1000-2A	YO31-1F
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	30		30				X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1274					1274			
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	60		60				X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/8, TWISTED, SHIELDED	FOOT	1385								
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4		4				* XX005372	POLYUREA PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	225	225							
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	6		6				* XX005733	POLYUREA PAVEMENT MARKING - LINE 12"	FOOT	100	100							
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2		2				* XX006058	POLYUREA PAVEMENT MARKING - LINE 4"	FOOT	9450	9450							
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10		10				* XX006059	POLYUREA PAVEMENT MARKING - LINE 6"	FOOT	800	800							
88500100	INDUCTIVE LOOP DETECTOR	EACH	8		8				* XX006061	POLYUREA PAVEMENT MARKING - LINE 24"	FOOT	105	105							
88600100	DETECTOR LOOP, TYPE I	FOOT	1232		1232				* XX006257	RECESSED REFLECTIVE PAVMENT MARKER	EACH	110	110							
88700200	LIGHT DETECTOR	EACH	4						XX006661	UNINTERRUPTABLE POWER SUPPLY	EACH	1			1					
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1						XX006697	LUMINAIRE (SPECIAL)	EACH	17							17	
89502380	REMOVE EXISTING HANDHOLE	EACH	1		1				Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1							
89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	12		12				Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1	1							
X0321630	LIGHTING CONTROLLER, CONSOLE TYPE	EACH	1						Z0022800	FENCE REMOVAL	FOOT	1700	1700							
X0322118	REMOVE CONCRETE FLARED END SECTIONS	EACH	4	4					X0325713	GROUND ROD	EACH	13							13	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103					X0325714	POST MOUNTED FLASHING BEACON, SOLAR POWERED INSTALLATION	EACH	6			6					
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	4531			4531			X2210384	UNIT DUCT WITH 3-1/8 NO. 4 AND 1/8 NO. 6 GROUND, 600V, (EPR-TYPE RHW) IN 1 1/4" DIAMETER SCHEDULE 40 POLYETHYLENE DUCT	FOOT	2800							2800	
X0324387	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	17						X0325716	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE 2) 3-1/8 NO. 2	FOOT	100							100	
X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	5	5					X0325715	REOPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1			1					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	651	651					* Z0076600	TRAINEEES	HOUR	1000	1000							
X5013800	PIPE CULVERT REMOVAL	EACH	6	6																
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1															
X8102010	CONDUIT PUSHED, 3" DIA., RIGID GALVANIZED STEEL	FOOT	350																	350
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	4543			4543														
X8710025	FIBER OPTIC CABLE ON MESSENGER, NO. 62.5/125, MM12F SM12F	FOOT	347			347														

* SPECIALTY ITEM

△ NON-PARTICIPATING
© Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

2/13/2007 10:05:08 AM