CONTRACT NO. 62895

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS	WILL	334	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NO.	ITEM	UNIT	URBAN ** TOTAL QUANTITY	ROADWAY I000-2A	PROP IL 59 099-4642 X271-2A	EXIST IL 59 099-0030 SFTY-2A	US 52 099-0139 SFTY-2A	SIGNING Y002-1C		LIGHTING Y030-1E
XX002870	AGGREGATE SHOULDERS, TYPE B (SPECIAL)	SQ YD	11102	11102						
XX003988	TEMPORARY CONCRETE BARRIER REMOVAL	FOOT	268	268						
XX005472	DRAINAGE STRUCTURE SPECIAL	EACH	4	4						
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	99436	99436						
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1						
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5						
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1						
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	9	9						
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	6	6						
Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	4	4						
Z0068400	STEEL CASINGS 42"	FOOT	40	40						
⊙ Z0076600	TRAINEES	HOUR	4000	4000						
35501288	HOT-MIX ASPHALT BASE COURSE, 2 1/2"	SQ. YD	89656	89656						
X0325733	TEMPORARY ASPHALT WEDGE	SQ YD	2147	2147						
X0325741	REINFORCED CONCRETE PIPE ELBOW, SPAN 30 RISE 19	EACH	4	4						
* XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	7							7
* X0325740	UNIT DUCT, 600V, 3-1/C NO. 2, 1/C NO. 4 GROUND, (EPR-TYPE RHW), 1 1/2" DIA. POLYETHYLENE	FOOT	1635							1635

⊙ Y080
* SPECIALTY ITEMS
** URBAN, 90% FEDERAL, 10% STATE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (I-80 TO BLACK ROAD)
WIDENING AND RESURFACING

SUMMARY OF QUANTITIES
V

SCALE: N.T.S. DRAWN BY AG
DATE 03/22/07 CHECKED BY DDH

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

Rev

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
USER NAME = $USER$
..\BD99IA001.DGN,..\SD061A001.DGN,..\SD061A001.DGN
3-21-2007,15:18:22 GARCIAAZ S:\DOCUMENT\02361501\CIVIL\DGN\SD061A005.SHT