

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS	WILL	334	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

CONTINUED FROM SHEET NO. 18

HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	STATION	LENGTH FT	LENG+20% +2' FT	WIDTH FT	BIT. REM./ PATCH SQ YD	TONS/SQ. YD. 3-1/2" Thick	Sub totals
	194+04.21	4.00	6.80	5.00	3.778	0.196	0.74
	193+60.32	4.00	6.80	5.00	3.778	0.196	0.74
	191+31.46	4.00	6.80	5.00	3.778	0.196	0.74
	190+83.34	7.00	10.40	5.00	5.778	0.196	1.13
	189+55.21	4.00	6.80	7.00	5.289	0.196	1.04
	189+09.99	4.00	6.80	5.00	3.778	0.196	0.74
	188+09.17	5.00	8.00	7.00	6.222	0.196	1.22
	188+04.81	5.00	8.00	5.00	4.444	0.196	0.87
S.B. LANE 2							
	358+90.34	6.00	9.20	4.00	4.089	0.196	0.80
	346+75.84	4.00	6.80	5.00	3.778	0.196	0.74
	341+60.55	4.00	6.80	4.00	3.022	0.196	0.59
	336+56.93	6.00	9.20	5.00	5.111	0.196	1.00
	328+18.50	4.00	6.80	4.00	3.022	0.196	0.59
	312+21.58	6.00	9.20	5.00	5.111	0.196	1.00
	309+12.63	4.00	6.80	5.00	3.778	0.196	0.74
	308+14.68	6.00	9.20	5.00	5.111	0.196	1.00
	307+13.78	6.00	9.20	5.00	5.111	0.196	1.00
	297+11.43	6.00	9.20	5.00	5.111	0.196	1.00
	291+14.14	5.00	8.00	5.00	4.444	0.196	0.87
	277+09.03	4.00	6.80	5.00	3.778	0.196	0.74
	270+36.89	10.00	14.00	3.00	4.667	0.196	0.91
	268+38.49	5.00	8.00	4.00	3.556	0.196	0.70
	258+31.36	4.00	6.80	5.00	3.778	0.196	0.74
	255+29.79	9.00	12.80	4.00	5.689	0.196	1.12
	254+29.21	4.00	6.80	5.00	3.778	0.196	0.74
	244+65.62	4.00	6.80	5.00	3.778	0.196	0.74
	242+25.01	4.00	6.80	5.00	3.778	0.196	0.74
	228+06.09	4.00	6.80	5.00	3.778	0.196	0.74
	218+04.05	5.00	8.00	5.00	4.444	0.196	0.87
NB LANE 1							
	130+75.45	4.00	6.80	7.00	5.289	0.196	1.04
	132+65.04	4.00	6.80	5.00	3.778	0.196	0.74
	133+93.26	4.00	6.80	5.00	3.778	0.196	0.74
	137+95.07	4.00	6.80	7.00	5.289	0.196	1.04
	188+20.46	4.00	6.80	7.00	5.289	0.196	1.04
	190+51.36	4.00	6.80	5.00	3.778	0.196	0.74
	197+48.94	4.00	6.80	7.00	5.289	0.196	1.04
	198+00.69	4.00	6.80	5.00	3.778	0.196	0.74
	201+54.78	4.00	6.80	7.00	5.289	0.196	1.04
	212+27.45	4.00	6.80	5.00	3.778	0.196	0.74
	221+68.48	4.00	6.80	5.00	3.778	0.196	0.74
	227+69.32	4.00	6.80	7.00	5.289	0.196	1.04
	231+94.91	5.00	8.00	7.00	6.222	0.196	1.22
	231+97.70	5.00	8.00	5.00	4.444	0.196	0.87
	233+67.76	4.00	6.80	5.00	3.778	0.196	0.74
	235+70.94	4.00	6.80	7.00	5.289	0.196	1.04
	238+93.99	4.00	6.80	7.00	5.289	0.196	1.04
	239+50.26	4.00	6.80	5.00	3.778	0.196	0.74
	241+75.39	4.00	6.80	7.00	5.289	0.196	1.04
	243+07.57	4.00	6.80	5.00	3.778	0.196	0.74
	243+69.65	4.00	6.80	7.00	5.289	0.196	1.04
	244+41.39	4.00	6.80	7.00	5.289	0.196	1.04
	245+69.41	4.00	6.80	7.00	5.289	0.196	1.04
	246+93.68	4.00	6.80	7.00	5.289	0.196	1.04
	247+70.79	4.00	6.80	7.00	5.289	0.196	1.04
	248+21.03	4.00	6.80	7.00	5.289	0.196	1.04
	248+71.24	4.00	6.80	7.00	5.289	0.196	1.04
	250+49.26	4.00	6.80	7.00	5.289	0.196	1.04
	250+82.32	4.00	6.80	5.00	3.778	0.196	0.74
	250+99.22	4.00	6.80	7.00	5.289	0.196	1.04
	251+31.56	4.00	6.80	5.00	3.778	0.196	0.74

CONTINUED IN THE NEXT COLUMN

CONTINUED FROM PREVIOUS COLUMN

STATION	LENGTH FT	LENG+20% +2' FT	WIDTH FT	BIT. REM./ PATCH SQ YD	TONS/SQ. YD. 3-1/2" Thick	Sub totals	
	293+61.62	4.00	6.80	7.00	5.289	0.196	1.04
	296+37.04	4.00	6.80	5.00	3.778	0.196	0.74
	296+59.78	4.00	6.80	7.00	5.289	0.196	1.04
	318+43.52	4.00	6.80	5.00	3.778	0.196	0.74
	399+61.31	4.00	6.8	5.00	3.778	0.196	0.74
NB LANE 2							
	TOTAL LENGTH	0.00	0.00	0.00	0.000	0.196	0.00
CLASS D PATCHES TYPE 11, 10"							
S.B. LANE 1							
	394+21.34	6.00	9.20	7.00	7.156	0.196	1.40
	381+07.87	6.00	9.20	7.00	7.156	0.196	1.40
	366+98.82	8.00	11.60	7.00	9.022	0.196	1.77
	366+90.85	8.00	11.60	5.00	6.444	0.196	1.26
	355+93.60	7.00	10.40	7.00	8.089	0.196	1.59
	351+94.28	10.00	14.00	7.00	10.889	0.196	2.13
	351+84.43	10.00	14.00	5.00	7.778	0.196	1.52
	336+36.09	7.00	10.40	7.00	8.089	0.196	1.59
	321+19.01	9.00	12.80	5.00	7.111	0.196	1.39
	317+73.93	6.00	9.20	7.00	7.156	0.196	1.40
	306+13.80	8.00	11.60	5.00	6.444	0.196	1.26
	300+17.53	6.00	9.20	7.00	7.156	0.196	1.40
	280+40.67	8.00	11.60	5.00	6.444	0.196	1.26
	272+45.22	11.00	15.20	7.00	11.822	0.196	2.32
	272+34.94	11.00	15.20	5.00	8.444	0.196	1.66
	265+39.46	6.00	9.20	7.00	7.156	0.196	1.40
	255+27.33	10.00	14.00	5.00	7.778	0.196	1.52
	243+22.05	10.00	14.00	5.00	7.778	0.196	1.52
	233+23.91	7.00	10.40	7.00	8.089	0.196	1.59
	202+08.77	7.00	10.40	7.00	8.089	0.196	1.59
	200+05.12	7.00	10.40	7.00	8.089	0.196	1.59
	195+14.68	8.00	11.60	7.00	9.022	0.196	1.77
	195+07.25	8.00	11.60	5.00	6.444	0.196	1.26
	192+61.47	8.00	11.60	5.00	6.444	0.196	1.26
	190+90.11	7.00	10.40	7.00	8.089	0.196	1.59
	187+11.51	10.00	14.00	7.00	10.889	0.196	2.13
	187+02.25	10.00	14.00	5.00	7.778	0.196	1.52
SB LANE 2							
	396+21.88	4.50	7.40	12.00	9.867	0.196	1.93
	391+14.66	6.00	9.20	12.00	12.267	0.196	2.40
	386+06.43	8.00	11.60	12.00	15.467	0.196	3.03
	385+04.50	8.00	11.60	12.00	15.467	0.196	3.03
	383+06.51	6.00	9.20	12.00	12.267	0.196	2.40
	381+02.59	8.00	11.60	12.00	15.467	0.196	3.03
	380+06.45	5.00	8.00	12.00	10.667	0.196	2.09
	378+05.65	4.00	6.80	12.00	9.067	0.196	1.78
	369+96.52	8.00	11.60	12.00	15.467	0.196	3.03
	368+98.60	4.50	7.40	12.00	9.867	0.196	1.93
	366+98.82	6.00	9.20	12.00	12.267	0.196	2.40
	362+90.88	9.00	12.80	12.00	17.067	0.196	3.35
	359+86.87	10.00	14.00	4.00	6.222	0.196	1.22
	356+90.83	5.00	8.00	12.00	10.667	0.196	2.09
	353+89.66	4.00	6.80	12.00	9.067	0.196	1.78
	336+27.43	4.00	6.80	12.00	9.067	0.196	1.78
	330+27.10	8.00	11.60	12.00	15.467	0.196	3.03
	325+22.35	7.00	10.40	12.00	13.867	0.196	2.72
	324+22.89	8.00	11.60	12.00	15.467	0.196	3.03
	322+21.70	5.00	8.00	12.00	10.667	0.196	2.09
	321+22.59	5.00	8.00	12.00	10.667	0.196	2.09
	320+17.52	12.00	16.40	5.00	9.111	0.196	1.79
	319+24.40	4.50	7.40	12.00	9.867	0.196	1.93
	318+22.28	4.50	7.40	12.00	9.867	0.196	1.93
	317+18.84	6.00	9.20	12.00	12.267	0.196	2.40
	306+13.80	6.00	9.20	12.00	12.267	0.196	2.40
	300+17.53	6.00	9.20	12.00	12.267	0.196	2.40
	296+12.25	4.00	6.80	12.00	9.067	0.196	1.78
	283+42.90	4.00	6.80	12.00	9.067	0.196	1.78
	282+43.92	4.00	6.80	12.00	9.067	0.196	1.78
	280+45.22	4.00	6.80	12.00	9.067	0.196	1.78
	279+45.18	4.00	6.80	12.00	9.067	0.196	1.78
	277+39.24	4.00	6.80	12.00	9.067	0.196	1.78
	275+34.45	11.00	15.20	5.00	8.444	0.196	1.66
	269+41.25	5.00	8.00	12.00	10.667	0.196	2.09
	267+38.05	5.00	8.00	12.00	10.667	0.196	2.09
	262+31.45	8.00	11.60	12.00	15.467	0.196	3.03
	253+28.52	5.00	8.00	12.00	10.667	0.196	2.09

CONTINUED IN THE NEXT COLUMN

CONTINUED FROM PREVIOUS COLUMN

STATION	LENGTH FT	LENG+20% +2' FT	WIDTH FT	BIT. REM./ PATCH SQ YD	TONS/SQ. YD. 3-1/2" Thick	Sub totals	
	252+27.61	8.00	11.60	12.00	15.467	0.196	3.03
	251+26.10	9.00	12.80	12.00	17.067	0.196	3.35
	250+26.83	7.00	10.40	12.00	13.867	0.196	2.72
	249+34.04	4.00	6.80	12.00	9.067	0.196	1.78
	248+26.12	5.00	8.00	12.00	10.667	0.196	2.09
	247+27.45	4.00	6.80	12.00	9.067	0.196	1.78
	246+24.32	7.00	10.40	12.00	13.867	0.196	2.72
	244+24.45	6.00	9.20	12.00	12.267	0.196	2.40
	243+24.10	7.50	11.00	12.00	14.667	0.196	2.87
	241+22.58	9.00	12.80	12.00	17.067	0.196	3.35
	240+22.80						