

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) WRS	WILL	334	27
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

THERMOPLASTIC PAVEMENT MARKING - LINE 4"					TOTAL	73,180.00	FOOT
LOCATION	FROM STA.	TO STA.	LENGTH FT		Sub	totals	
Mainline 4" YELLOW THERMOPLASTIC PAVEMENT MARKING							
S.B. Lt. Edge	186+03.60	402+65.07	21,661.47		21,661.47		
Mainline 4" YELLOW THERMOPLASTIC PAVEMENT MARKING							
S.B. Rt. Edge	194+66.40	205+07.66	1,041.26		1,041.26		
S.B. Rt. Edge	213+67.51	226+36.22	1,268.71		1,268.71		
S.B. Rt. Edge	240+90.00	276+23.00	3,533.00		3,533.00		
S.B. Rt. Edge	284+75.35	325+09.00	4,033.65		4,033.65		
S.B. Rt. Edge	336+74.11	352+21.75	1,547.64		1,547.64		
S.B. Rt. Edge	360+64.00	402+65.07	4,201.07		4,201.07		
Mainline 4" YELLOW THERMOPLASTIC PAVEMENT MARKING							
N.B. Lt. Edge	187+28.30	402+65.07	21,536.77		21,536.77		
Mainline 4" WHITE THERMOPLASTIC PAVEMENT MARKING							
N.B. Rt. Edge	193+08.00	205+77.69	1,269.69		1,269.69		
N.B. Rt. Edge	214+57.77	217+14.00	256.23		256.23		
N.B. Rt. Edge	242+59.00	269+52.00	2,693.00		2,693.00		
N.B. Rt. Edge	280+90.67	327+61.00	4,670.33		4,670.33		
N.B. Rt. Edge	336+25.88	351+27.73	1,501.85		1,501.85		
N.B. Rt. Edge	363+00.00	402+65.07	3,965.07		3,965.07		

THERMOPLASTIC PAVEMENT MARKING - LINE 8"					TOTAL	22,325	FOOT
LOCATION	FROM STA.	TO STA.	LENGTH FT		Sub	totals	
RAMP EDGE							
S.B.	186+04.00	194+66.40	862.4	I - 80	862.4		
N.B.	187+28.00	189+16.00	188.0	I - 80	188.0		
S.B.	205+07.66	213+67.51	859.8	I - 80	859.8		
N.B.	205+77.69	214+57.77	880.1	I - 80	880.1		
S.B.	226+36.22	240+90.00	1,453.8	I - 80	1,453.8		
N.B.	223+18.81	242+59.00	1,940.2	I - 80	1,940.2		
N.B.	276+23.00	284+75.35	852.3	IL 59	852.3		
N.B.	269+52.00	280+90.67	1,138.7	IL 59	1,138.7		
S.B.	325+09.00	336+74.11	1,165.1	U.S. 52	1,165.1		
N.B.	327+61.00	336+25.88	864.9	U.S. 52	864.9		
N.B.	351+27.75	363+00.00	1,172.3	U.S. 52	1,172.3		
S.B.	352+21.75	360+64.00	842.3	U.S. 52	842.3		
GORE							
S.B.	190+14.20	194+66.40	452.2	I - 80	452.2		
N.B.	188+73.40	193+08.00	434.6	I - 80	434.6		
S.B.	205+07.66	206+65.00	157.3	I - 80	157.3		
S.B.	212+85.75	213+67.51	81.8	I - 80	81.8		
N.B.	205+77.69	206+76.00	98.3	I - 80	98.3		
N.B.	213+44.00	214+57.77	113.8	I - 80	113.8		
S.B.	226+36.22	231+00.00	463.8	I - 80	463.8		
N.B.	223+18.81	234+59.00	1,140.2	I - 80	1,140.2		
S.B.	281+37.00	284+75.35	338.3	IL 59	338.3		
N.B.	276+71.84	280+90.67	418.8	IL 59	418.8		
S.B.	334+30.00	336+74.11	244.1	U.S. 52	244.1		
N.B.	333+50.00	336+25.88	275.9	U.S. 52	275.9		
N.B.	351+27.75	354+09.00	281.3	U.S. 52	281.3		
S.B.	352+21.75	354+71.66	249.9	U.S. 52	249.9		
MAINLINE							
S.B.	190+14.02	194+66.02	452.0	I - 80	452.0		
N.B.	188+73.40	193+08.00	434.6	I - 80	434.6		
S.B.	205+07.66	206+65.00	157.3	I - 80	157.3		
S.B.	212+85.75	213+67.51	81.8	I - 80	81.8		
N.B.	205+77.69	206+76.00	98.3	I - 80	98.3		
N.B.	213+44.00	214+57.77	113.8	I - 80	113.8		
S.B.	226+36.22	231+00.00	463.8	I - 80	463.8		
N.B.	217+14.00	234+59.00	1,745.0	I - 80	1,745.0		
S.B.	281+37.00	284+75.35	338.3	IL 59	338.3		
N.B.	276+71.84	280+90.67	418.8	IL 59	418.8		
S.B.	334+30.00	336+74.11	244.1	U.S. 52	244.1		
N.B.	333+50.00	336+25.88	275.9	U.S. 52	275.9		
N.B.	351+27.75	354+09.00	281.3	U.S. 52	281.3		
S.B.	352+21.75	354+71.66	249.9	U.S. 52	249.9		

THERMOPLASTIC PAVEMENT MARKING - LINE 12"								TOTAL	4,246.0	FOOT
LOCATION	FROM STA.	TO STA.	DISTANCE	SPACING 500' - SHLD 30' - GORE (# OF LINES)	LENGTH SHLD. LINE	TOTAL LENGTH	Sub	totals		
N.B. RT. SHLD.										
N.B. RT. GORE	213+44.00	214+57.71		4.00	GORE	73.59		73.59		
N.B. RT. SHLD.	214+57.77	217+14.00	256.23	0.51	14.1	7.23		7.23		
N.B. RT. GORE	217+14.00	223+18.81		20.00	GORE	191.7		191.7		
N.B. RT. SHLD.	242+59.00	276+71.84	3412.84	6.83	14.1	96.24		96.24		
N.B. RT. GORE	223+18.81	234+59.00		35.00		647.1		647.1		
N.B. RT. GORE										
N.B. RT. GORE	276+71.84	280+90.67		11.00	GORE	212.7		212.7		
N.B. RT. SHLD.	280+90.67	327+61.00	4670.33	9.34	14.1	131.70		131.70		
N.B. RT. GORE	333+50.00	336+25.88		7.00	GORE	126.9		126.9		
N.B. RT. SHLD.	336+25.88	351+27.75	1501.87	3.00	14.1	42.35		42.35		
N.B. RT. GORE	351+27.75	354+09.00	281.25	5.00	GORE	68.5		68.5		
N.B. RT. SHLD.	354+09.00	402+65.07	4856.07	9.71	14.1	136.94		136.94		
N.B. LT. SHLD.	213+51.00	402+65.07	18914.07	37.83	9.2	348.02		348.02		
N.B. LT. SHLD.	187+28.30	213+51.00	2622.70	5.25	14.1	73.96		73.96		
S.B. RT. GORE	190+14.20	194+66.40	452.20	13.00	GORE	107.5		107.5		
S.B. RT. SHLD.	186+04.00	205+07.66	1903.66	3.81	14.1	53.68		53.68		
S.B. RT. GORE										
S.B. RT. GORE	226+36.22	231+00.00		12.00	GORE	259.7		259.7		
S.B. RT. SHLD.	231+00.00	281+37.00	5037.00	10.07	14.1	142.04		142.04		
S.B. RT. GORE	281+37.00	284+75.35		8.00	GORE	124.4		124.4		
S.B. RT. SHLD.	284+75.35	334+30.00	4954.65	9.91	14.1	139.72		139.72		
S.B. RT. GORE	334+30.00	336+74.11		5.00	GORE	73.7		73.7		
S.B. RT. SHLD.	336+74.11	352+21.75	1547.64	3.10	14.1	43.64		43.64		
S.B. RT. GORE	352+21.75	354+71.66		6.00	GORE	109.2		109.2		
S.B. RT. SHLD.	354+71.66	402+65.07	4793.41	9.59	14.1	135.17		135.17		
S.B. LT. SHLD.	213+51.00	402+65.07	18914.07	37.83	9.2	348.02		348.02		
S.B. LT. SHLD.	186+03.60	213+51.00	2747.40	5.49	14.1	77.48		77.48		

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"							TOTAL	467	FOOT
LOCATION	FROM STA.	TO STA.	LENGTH		%	Sub	totals		
DOTTED LINES for AUXILIARY LANES 6' - SKIP 2' - DASH									
N.B.	206+75.00	213+44.00	669.00		25%	167.3		167.3	
S.B.	206+65.00	212+85.77	620.77		25%	155.2		155.2	
S.B.	276+22.93	281+99.68	576.75		25%	144.2		144.2	

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"							TOTAL	22,081.0	FOOT
LOCATION	FROM STA.	TO STA.	LENGTH	ADJUSTMENT FACTOR		Sub	totals		
LANE LINES - 10' DASH 30' SKIP									
N.B. left	187+28.30	402+65.07	21,536.8	25%		5,384.2		5,384.2	
N.B. right	187+28.30	402+65.07	21,536.8	25%		5,384.2		5,384.2	
N.B. outside	213+44.00	217+00.00	356.0	25%		89.0		89.0	
	234+59.00	237+25.00	266.0	25%		66.5		66.5	
	274+62.00	276+71.84	209.8	25%		52.5		52.5	
	332+00.00	333+50.00	150.0	25%		37.5		37.5	
	354+09.00	357+05.00	296.0	25%		74.0		74.0	
S.B. left	186+03.60	402+65.07	21,661.5	25%		5,415.4		5,415.4	
S.B. right	186+03.60	402+65.07	21,661.5	25%		5,415.4		5,415.4	
S.B. outside	231+00.00	234+60.00	360.0	25%		90.0		90.0	
	333+10.00	334+30.00	120.0	25%		30.0		30.0	
	354+71.66	356+43.00	171.3	25%		42.8		42.8	

EPOXY PAVEMENT MARKING - LINE 4"							TOTAL	5,326.6	FOOT
LOCATION	FROM STATION	TO STATION	LENGTH	TYPE	ADJ. FACTOR	Sub	totals		
WINTER SHUTDOWN									
N.B. RT EDGE LINE	193+08.00	205+77.65	1,269.7	SOLID	100%	1,269.7		1,269.7	
N.B. AUX LANE	206+75.00	213+44.00	669.0	SKIP	25%	167.3		167.3	
N.B. RT EDGE LINE	214+57.71	218+95.00	437.3	SOLID	100%	437.3		437.3	
N.B. LT EDGE LINE	187+29.00	218+95.00	3,166.0	SOLID	100%	3,166.0		3,166.0	
S.B. RT EDGE LINE	194+52.31	205+05.00	1,052.7	SOLID	100%	1,052.7		1,052.7	
STAGE II									
N.B.	187+28.31	402+65.07	21,536.8	SOLID	100%	21,536.8		21,536.8	
S.B.	186+03.63	402+65.07	21,661.4	SOLID	100%	21,661.4		21,661.4	

EPOXY PAVEMENT MARKING - LINE 5"							TOTAL	3,459.9	FOOT
LOCATION	FROM STATION	TO STATION	LENGTH	TYPE	ADJ. FACTOR	Sub	totals		
WINTER SHUTDOWN									
N.B. LANE LINE	187+29.00	218+95.00	3,166.0	SKIP-DASH	25%	791.5		791.5	
N.B. RT AUX	213+44.00	217+00.00	356.0	SKIP-DASH	25%	89.0		89.0	
S.B. LANE LINE	186+04.00	218+95.00	3,291.0	SKIP-DASH	25%	822.8		822.8	
STAGE II									
N.B.	187+28.31	205+50.01	1,821.7	SKIP-DASH	25%	455.4		455.4	
N.B.	205+50.01	214+50.00	900.0	SOLID	100%	900.0		900.0	
N.B.	214+50.00	262+50.00	4,800.0	SKIP-DASH	25%	1,200.0		1,200.0	
N.B.	262+50.00	304+50.00	4,200.0</						