

Table with project details: F.A.I. RTE., SECTION, COUNTY, TOTAL SHEETS, SHEET NO., STA. TO STA., FED. ROAD DIST. NO., ILLINOIS, FED. AID PROJECT.

SCHEDULE OF QUANTITIES

Table 1: POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80. Includes columns for LOCATION, FROM STA., TO STA., LENGTH, WIDTH FT, AREA SQ FT, SQ YD, LBS/SY, and Sub Totals. Total: 25991 TON.

Table 2: POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80. Includes columns for LOCATION, FROM STA., TO STA., MEA AREA SQ FT, SQ YD, LBS/SY, and Sub Totals. Total: 21619 TON.

Table 3: RESURFACING OF EXISTING LANES. Includes columns for LOCATION, STA., WIDTH, STA., LENGTH, AVG. WIDTH, SQ FT, SQ YD, LBS/SY, and Sub Totals.

Table 4: ADDITIONAL QUANTITIES FOR WEDGES. Includes columns for LOCATION, STA., OFFSET, STA., OFFSET, LENGTH, WIDTH FT, AREA SQ FT, AREA SQ YD, LBS/SY, and Sub Totals.

Table 5: CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT. Includes columns for LOCATION, FROM STATION, TO STATION, LENGTH (FT), OFFSET, and Sub Totals. Total: 519 FOOT.

Table 6: CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT. Includes columns for LOCATION, FROM STATION, TO STATION, LENGTH (FT), and Sub Totals. Total: 19259 FOOT.

Table 7: CHANGEABLE MESSAGE SIGN. Includes columns for LOCATION, LENGTH (FT), CAL MO, and Sub Totals. Total: 54 CAL MO.

Table 8: AGGREGATE SHOULDERS, TYPE B (SPECIAL). Includes columns for LOCATION, FROM STA., TO STA., LENGTH, X3, SQ FT, X/9, and Sub Totals. Total: 11,102.00 SQ YD.

Table 9: AGGREGATE SUBGRADE 12". Includes columns for LOCATION, FROM STATION, TO STATION, WIDTH FT, AREA SQ FT, SQ YD, and Sub Totals. Total: 99436 SQ YD.

Table 10: IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3. Includes columns for LOCATION, STATION, and Sub Totals. Total: 1 EACH.

Table 11: SAND MODULE IMPACT ATTENUATOR TO BE REMOVED. Includes columns for APPROXIMATE STATION, LOCATION, END OF PIER (N/S), and Sub Totals. Total: 4 EACH.

Table 12: HOT-MIX ASPHALT BASE COURSE, 2 1/2". Includes columns for LOCATION, STATION, STATION, LENGTH (FT), WIDTH (FT), AREA (SQ FT), MEASURE AREA SQ FT, AREA/S, and Sub Totals. Total: 89656 SQ. YD.

PLOT DATE # 06/21/2007
FILE NAME # SCHEDULE
PLOT SCALE # 3/4"=1'-0"
USER NAME # MUSER

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (I-80 TO BLACK ROAD)
WIDENING AND RESURFACING
SCHEDULE OF QUANTITIES
XVI
SCALE: N.T.S.
DATE 03/22/07
DRAWN BY JFS
CHECKED BY DDH
TENGO ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS