

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) WRS	WILL	334	31A
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTINUED FROM SHEET 31

HOT-MIX ASPHALT BASE COURSE, 2 1/2"								TOTAL	89656	SQ. YD.
LOCATION	STATION	STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ FT)	MEASURE AREA SQ FT	AREA/9		Sub totals	
ML	CONC. BAR. 2F									
ML	216+37.60	228+99.37	1,261.77	3.0	3,785.31		9.0		-420.59	
ML	CONC. BAR. TRANS									
ML	228+99.37	229+70.67				278.40	9.0		-30.93	
ML	229+81.37	230+52.62				278.40	9.0		-30.93	
ML	CONC. BAR. 2F									
ML	230+52.62	247+45.37	1,692.75	3.0	5,078.25		9.0		-564.25	
ML	CONC. BAR. TRANS									
ML	247+45.37	248+16.62				278.40	9.0		-30.93	
ML	248+27.37	248+98.62				278.40	9.0		-30.93	
ML	CONC. BAR. 2F									
ML	248+98.62	255+49.37	650.75	3.0	1,952.25		9.0		-216.92	
ML	CONC. BAR. TRANS									
ML	255+49.37	256+20.62				278.40	9.0		-30.93	
ML	256+31.37	257+02.62				278.40	9.0		-30.93	
ML	CONC. BAR. 2F									
ML	257+02.62	267+89.33	1,086.71	3.0	3,260.13		9.0		-362.24	
ML	CONC. BAR. TRANS + CONC. BAR. 1F									
ML	267+89.33	270+49.72				1,237.20	9.0		-137.47	
ML	270+51.15	272+44.04				882.10	9.0		-98.01	
ML	CONC. BAR. 2F									
ML	272+44.04	294+89.78	2,245.74	3.0	6,737.22		9.0		-748.58	
ML	CONC. BAR. TRANS									
ML	294+89.78	295+78.33				238.20	9.0		-26.47	
ML	296+23.66	297+06.91				223.40	9.0		24.82	
ML	CONC. BAR. 2F									
ML	297+06.91	332+98.37	3,591.46	3.0	10,774.38		9.0		-1,197.15	
ML	CONC. BAR. TRANS									
ML	332+98.37	333+69.62				278.40	9.0		-30.93	
ML	333+80.37	334+51.62				278.40	9.0		-30.93	
ML	CONC. BAR. 2F									
ML	334+51.62	343+19.45	867.80	3.0	2,603.40		9.0		-289.27	
ML	CONC. BAR. TRANS									
ML	343+19.45	343+60.70		3.0		133.40	9.0		-14.82	
ML	344+34.71	344+75.21		3.0		130.90	9.0		-14.54	
ML	CONC. BAR. 2F									
ML	344+75.21	353+78.36	903.15	3.0	2,709.45		9.0		-301.05	
ML	CONC. BAR. TRANS									
ML	353+78.36	354+49.61				278.40	9.0		-30.93	
ML	354+60.36	355+31.61				278.40	9.0		-30.93	
ML	CONC. BAR. 2F									
ML	355+31.61	402+31.67	4,700.06	3.0	14,100.18		9.0		-1,566.69	
ML	CONC. BAR. TRANS									
ML	402+31.67	402+65.07				88.10	9.0		-9.79	
MINUS THE AREA OF THE CONCRETE GUTTER										
			WIDTH	LENGTH	AREA					
			FT	FT	SQ FT	SQ YD				
			0.83	28,196.00	23,402.68	2,600.30	-2,600.30			

TEMPORARY ASPHALT WEDGE							TOTAL	2147	SQ YD
DIRECTION	STATION	STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ FT)			SUB TOTALS	
S.B.	186+03.00	210+81.00	2478.0	4.0	9912.0			1101.3	
N.B.	187+28.00	210+81.00	2353.0	4.0	9412.0			1045.8	

HOT-MIX ASPHALT BASE COURSE, 1 1/2"					TOTAL	3262	SQ YD
LOCATION	STATION	STATION	MEASURE AREA SQ FT			Sub totals	
S.B. Accident Investigation Site							
	5261+13.78	5266+41.32	15,861.00				
			407.40				
			15,453.60			1,717.07	
N.B. Accident Investigation Site							
	5211+32.63	5216+00.96	14,302.00				
	SUBTRACT: CONC. MED. TSM.		395.50				
			13,906.50			1,545.17	

PLOT DATE = #DATE*
 FILE NAME = #FILE#*
 PLOT SCALE = #SCALE#*
 USER NAME = #USER#*
 \\SC06J003.DGN, A:\0\PHARM\LDN, \SC06J003.DGN
 3-22-2007, 1:20:15
 G:\ACTRAZ SA\DOCUMENT\B2R\B5R\CTVIL.DGN SC06J003.DGN

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 55 (I-80 TO BLACK ROAD)
 WIDENING AND RESURFACING

SCHEDULE OF QUANTITIES XVII

SCALE: N.T.S. DRAWN BY JFS
 DATE 03/22/07 CHECKED BY DDH

TENG TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS