

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) WRS	WILL	334	231
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

**SCHEDULE OF QUANTITIES - SIGNING**

PAY ITEM	SIGN PANEL, TY 3 AND STRUCTURES										
	SIGN NO.		1G099I055L249.0		SIGN PANEL ASSEMBLY	SIGN PANEL	SIGN PANEL ASSEMBLY	SIGN PANEL ASSEMBLY	MILEPOST MARKER ASSEMBLY	SIGN PANEL ASSEMBLY	SIGN PANEL ASSEMBLY
	STATION		139+80		MP 248.97	TYPE 3	TYPE 3	TYPE 2	TYPE B	TYPE A	TYPE B
	SIZE (WIDTHxHEIGHT)		10'x5'		INSTALLATION	REMOVAL	INSTALLATION	REMOVAL	INSTALLATION	REMOVAL	RELOCATE
	TOTAL QUANTITY	UNIT	INSTALLATION	REMOVAL	INSTALLATION	REMOVAL	INSTALLATION	REMOVAL	INSTALLATION	REMOVAL	RELOCATE
REINFORCEMENT BARS	160	POUND	160								
SIGN PANEL - TYPE 1	17	SQ FT					17				
SIGN PANEL - TYPE 2	431	SQ FT					431				
SIGN PANEL - TYPE 3	2530	SQ FT	50		2480						
REMOVE SIGN PANEL ASSEMBLY - TYPE A	9	EACH							9		
REMOVE SIGN PANEL ASSEMBLY - TYPE B	33	EACH						33			
REMOVE SIGN PANEL - TYPE 3	2018	SQ FT		50		1968					
RELOCATE SIGN PANEL ASSEMBLY - TYPE B	1	EACH									1
MILE POST MARKER ASSEMBLY	5	EACH						5			
STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	257	POUND	256.5								
WOOD SIGN SUPPORT	879	FOOT			410		469				
CONCRETE FOUNDATIONS	1.4	CU YD	1.4								
REMOVE GROUND-MOUNTED SIGN SUPPORT	2	EACH		2							
REMOVE CONCRETE FOUNDATION - GROUND MOUNT	2	EACH		2							

#DATE\*  
 #FILE#\*  
 #SCALE\*  
 #USER\*  
 SA:\DOCUMENT\02361501\CTVIL\UDN\SC061\026.SHT  
 VARGSHKZ  
 2-28-2007, 10:10:38

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI ROUTE 55 (I-80 TO BLACK ROAD)  
 WIDENING AND RESURFACING

**SCHEDULE OF QUANTITIES  
 SIGNING**

SCALE: N.T.S. DRAWN BY AG  
 DATE 02/23/07 CHECKED BY DH

**TENG** TENG & ASSOCIATES, INC.  
 ENGINEERS/ARCHITECTS/PLANNERS  
 CHICAGO, ILLINOIS