

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS-1	WILL	227	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
	SOQ-01 OF 6			

SUMMARY OF QUANTITIES				90% FED. / 10% STATE			
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE			Non-Participating
				ROADWAY	LOCKPORT	LIGHTING	
				Sta. 594+66.34 to Sta. 751+75.00	Sta. 684+31.15	Sta. 594+66.34 to Sta. 751+75.00	
				I000-2A	SFTY-2A	Y030-1E	
20200100	EARTH EXCAVATION	CU YD	9,650	9,650			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	13,425	13,425			
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	8,780	8,780			
20800150	TRENCH BACKFILL	CU YD	3,754	3,754			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	26,333	26,333			
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	475	475			
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	2,285	2,285			
25000210	SEEDING, CLASS 2A	ACRE	1.50	1.50			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	135	135			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	135	135			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	135	135			
25100630	EROSION CONTROL BLANKET	SQ YD	7,281	7,281			
25100115	MULCH, METHOD 2	ACRE	6.50	6.50			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	636	636			
28000300	TEMPORARY DITCH CHECKS	EACH	5	5			
28000500	INLET AND PIPE PROTECTION	EACH	6	6			
28000510	INLET FILTERS	EACH	81	81			
28100105	STONE RIPRAP, CLASS A3	SQ YD	40	40			
28200200	FILTER FABRIC	SQ YD	40	40			
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	7,131	7,131			
35300510	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2"	SQ YD	3,810	3,810			
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	36,486	36,486			
35501325	HOT-MIX ASPHALT BASE COURSE, 10 1/4"	SQ YD	235	235			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	127.1	127.1			
40600300	AGGREGATE (PRIME COAT)	TON	17.9	17.9			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	14.0	14.0			
40600895	CONSTRUCTING TEST STRIP	EACH	4	4			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	767	767			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	588.1	588.1			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19, N70	TON	1,384	1,384			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,156	2,156			
44000100	PAVEMENT REMOVAL	SQ YD	3,576	3,576			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 55
 US 30 (PLAINFIELD ROAD) TO 143RD STREET
 SUMMARY OF QUANTITIES



SCALE: NONE
 DATE: 02-23-07

DRAWN BY AR
 CHECKED BY SV

FINAL