

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) WRS-1	WILL	227	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
	SOQ-02	OF	6	

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	90% FED. / 10% STATE			Non-Participating 100% STATE
				CONSTRUCTION TYPE CODE			
				ROADWAY Sta. 594+66.34 to Sta. 751+75.00	LOCKPORT Sta. 684+31.15	LIGHTING Sta. 594+66.34 to Sta. 751+75.00	
				1000-2A	SFTY-2A	Y030-1E	
44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	46,800	46,800			
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	19,722	19,722			
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	2,925	2,925			
44002228	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 7"	SQ YD	23	23			
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	11,007	11,007			
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	234	234			
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1,521	1,521			
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	257	257			
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	351	351			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	53,674	53,674			
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	1,362	1,362			
50102400	CONCRETE REMOVAL	CU YD	0.9		0.9		
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	3			
50300225	CONCRETE STRUCTURES	CU YD	6.6		6.6		
50300300	PROTECTIVE COAT	SQ YD	3052	3,052			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	340		340		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3	3			
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1			
54215979	REINFORCED CONCRETE PIPE ELBOW, 24"	EACH	3	3			
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	3	3			
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	1			
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	1,176	1,176			
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	316	316			
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	74	74			
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	2,041	2,041			
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	1,473	1,473			
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	297	297			
55021900	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 21"	FOOT	839	839			
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	591	591			
55022100	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 27"	FOOT	297	297			
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	1,039	1,039			
55034200	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 23, RISE 14	FOOT	1,088	1,088			
55039700	STORM SEWERS TO BE CLEANED	FOOT	728				728

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 55
 US 30 (PLAINFIELD ROAD) TO 143RD STREET

SUMMARY OF QUANTITIES

SCALE: NONE
 DATE: 02-23-07

DRAWN BY: AR
 CHECKED BY: SJV

