

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS-1	WILL	227	9
STA. ....		TO STA. ....		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		SOQ-05 OF 6		

SUMMARY OF QUANTITIES				90% FED. / 10% STATE			Non-Participating
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY Sta. 594+66.34 to Sta. 751+75.00 I000-2A	LOCKPORT Sta. 684+31.15 SFTY-2A	LIGHTING Sta. 594+66.34 to Sta. 751+75.00 Y030-1E	
* 81603210	UNIT DUCT, 600V, 3-1/C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	2,141			2,141	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,994			1,994	
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	72			72	
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	8			8	
* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	2			2	
* 84200700	LIGHTING FOUNDATION REMOVAL	EACH	8			8	
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	8			8	
X0322054	REMOVAL OF PRECAST FLARED END SECTION	EACH	4	4			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1,300	1,300			
X0322323	WEED CONTROL, TEASEL	GALLON	2.5	2.5			
X0322729	MATERIAL TRANSFER DEVICE	TON	20,168	20,168			
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	27	27			
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CALMO	18			18	
X0323879	SERVICE PATROL	CAL DA	360	360			
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	3,382	3,382			
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	846	846			
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	6	6			
* X0324181	DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEAREST SPLICE	EACH	1			1	
X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2			
X0324774	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1,400	1,400			
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	350	350			
X0484300	MEDIAN INLET BOX REMOVAL	EACH	2	2			
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	10,084	10,084			
X4066685	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	10,084	10,084			
X6370940	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	8,792	8,792			
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	18	18			
X6700600	ENGINEER'S FIELD LABORATORY (SPECIAL)	CAL MO	18	18			
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1			
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	360	360			
XX002870	AGGREGATE SHOULDERS, TYPE B (SPECIAL)	SQ YD	5,983	5,983			
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	39,444	39,444			

\* SPECIALTY ITEMS



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI ROUTE 55  
 US 30 (PLAINFIELD ROAD) TO 143RD STREET

SUMMARY OF QUANTITIES

SCALE: NONE  
 DATE: 02-23-07

DRAWN BY AR  
 CHECKED BY SJV

FINAL