



CONTRACT NO. 62896				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS-1	WILL	227	100
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
PSCH 02 OF 02				

PIPE SCHEDULE

PIPE NUMBER	SHEET NUMBER	UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	TRENCH BACKFILL (CU YD)	STORM SEWER (FEET)										PIPE SLOPE		
					CLASS A												
					TYPE 1				TYPE 2								
					12 in	15 in	24 in	14"x23" ELL.	12 in	15 in	18 in	21 in	24 in	27 in		30 in	
82	DRU-8	85	89	3.6		25										0.32%	
83	DRU-8	87	89	0.7	3											1.00%	
84	DRU-8	89	88	11.6			54									0.11%	
85	DRU-9	90	89	29.1		122										0.11%	
86	DRU-9	91	87	28.4		122										0.10%	
87	DRU-9	92	90	65.6				247								0.11%	
88	DRU-9	93	91	53.2				230								0.22%	
89	DRU-9	94	92	87.1				297								0.37%	
90	DRU-9	95	93	98.4				314								0.02%	
91	DRU-9	96	94	151.5	297											0.05%	
92	DRU-9	97	95	91.3	297											0.67%	
93	DRU-9	98	96	51.6	163											0.44%	
94	DRU-9	99	97	37.6	163											0.44%	
95	DRU-10	100	102	66.5				297								0.45%	
96	DRU-10	101	103	65.3				297								0.49%	
97	DRU-10	102	104	67.5				297								0.57%	
98	DRU-10	103	105	66.3				297								0.53%	
99	DRU-10	104	EXIST	53.1					262							0.13%	
100	DRU-10	105	EXIST	79.4					272							0.45%	
TOTAL					3754	1176	316	74	1088	2041	1473	297	839	591	297	1039	

 	REVISIONS NAME DATE		ILLINOIS DEPARTMENT OF TRANSPORTATION FAI ROUTE 55 US 30 (PLAINFIELD ROAD) TO 143RD STREET DRAINAGE SCHEDULE - PIPES (2 OF 2) SCALE: 1" = 50' DATE: 02/23/2007
		DRAWN BY: JPA CHECKED BY: TEH	

FINAL