

STRUCTURE SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS-1	WILL	227	103
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
SSCH 02 OF 02				

STRUCTURE NUMBER	SHEET NUMBER	LOCATION			MANHOLES			REINFORCED CONCRETE PIPE ELBOW, 24"	PRECAST F.E.S.					CATCH BASINS			RIM ELEV	INVERT ELEVATIONS																				
					TYPE A									TYPE A																								
		STATION	OFFSET (FT)	SIDE	TY 1 F CL	TY 20 F&G			TY 20 F&G	TY 20 F&G	TY 20 F&G	TY 20 F&G	TY 20 F&G	TY 20 F&G	TY 20 F&G	TY 20 F&G		TY 20 F&G	TY 20 F&G	TY 20 F&G	TY 20 F&G	TY 20 F&G																
						4 FT	5 FT																6 FT	4 FT	5 FT	6 FT												
80	DRU 7	699+50	1.5	RT										1				624.60																				
81	DRU 8	723+50	1.5	LT										1				622.05	618.55																			
82	DRU 8	723+50	1.5	RT										1				622.10																				
83	DRU 8	726+00	1.5	LT										1				620.71	617.47																			
84	DRU 8	726+00	1.5	RT										1				620.72																				
85	DRU 8	726+50	1.5	LT										1				620.68	617.31																			
86	DRU 8	726+50	1.5	RT										1				620.67																				
87	DRU 8	726+75	1.5	RT											1			620.65	616.48																			
88	DRU 8	726+75	62.5	LT						1							618.39																					
89	DRU 8	726+75	1.5	LT											1			620.63	616.45																			
90	DRU 9	728+00	1.5	LT										1				620.84	616.58																			
91	DRU 9	728+00	1.5	RT										1				620.76	616.60																			
93	DRU 9	730+33.19	1.5	RT										1				621.34	617.10																			
92	DRU 9	730+50	1.5	LT										1				621.52	616.84																			
94	DRU 9	733+50	1.5	LT										1				622.65	617.95																			
95	DRU 9	733+50	1.5	RT										1				622.63	617.17																			
97	DRU 9	736+50	1.5	RT										1				623.45	619.16																			
96	DRU 9	736+50	1.5	LT										1				623.48	618.35																			
99	DRU 9	738+16	1.5	RT										1				623.88																				
98	DRU 9	738+16	1.5	LT										1				623.86																				
100	DRU 10	743+00	1.5	LT										1				623.50	619.40																			
101	DRU 10	743+00	1.5	RT										1				623.48	619.47																			
102	DRU 10	746+00	1.5	LT										1				622.11	618.05																			
103	DRU 10	746+00	1.5	RT										1				622.05	618.02																			
104	DRU 10	749+00	1.5	LT										1				620.47	616.10																			
105	DRU 10	749+00	1.5	RT										1				620.58	615.86																			
TOTALS					1	1	1		3	3				1				60	20																			



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 55
 US 30 (PLAINFIELD ROAD) TO 143RD STREET
DRAINAGE SCHEDULE - STRUCTURES
 (2 OF 2)
 SCALE: 1" = 50'
 DATE: 02/23/2007
 DRAWN BY: JPA
 CHECKED BY: TEH

FINAL