

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	100 (I&2) I-9	WILL	227	110
STA. 607+00		TO STA. 608+26.93		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
PVMRK - 2 OF 27				



END PROPOSED PAVEMENT MARKING AND SIGNING

MATCH EXISTING PAVEMENT MARKINGS

STA. 608+26.93

MATCH LINE STA. 607+00

EJ & E RAILROAD

- RAISED REFLECTIVE PAVEMENT MARKER, CLUSTER OF 2 CRYSTAL / OPAQUE @ 80FT C-C (TYP.)
- PREFORMED PLASTIC PAVEMENT MARKING, 5" (WHITE) 10FT DASH 30FT SKIP (TYP.)
- THERMOPLASTIC PAVEMENT MARKING 4" (YELLOW)
- THERMOPLASTIC PAVEMENT MARKING 8" (WHITE)

- THERMOPLASTIC PAVEMENT MARKING 4" (YELLOW)
- RAISED REFLECTIVE PAVEMENT MARKER, CLUSTER OF 2 CRYSTAL / OPAQUE @ 80FT C-C (TYP.)
- PREFORMED PLASTIC PAVEMENT MARKING, 5" (WHITE) 10FT DASH 30FT SKIP (TYP.)
- THERMOPLASTIC PAVEMENT MARKING 8" (WHITE)

EXIST. R.O.W.

PROPOSED ϕ I-55

SB I-55

I-615+00

NB I-55


I-620+00

EXIST. R.O.W.

EXIST. R.O.W.

EXIST

CONSTRUCTION RESUMES AT STA. 641+00
SEE PVMRK - 3



DAVID MASON & ASSOCIATES
Civil Engineering
Structural Engineering
Surveying
448 E. Illinois, Suite 640
Chicago, IL 60611
(312) 942-9600

PARSONS BRINCKERHOFF

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. I-55
US RTE. 30 TO 143rd STREET

PAVEMENT MARKING AND SIGNING PLANS

SCALE: 1" = 50'
DATE: FEBRUARY 23, 2007

DRAWN BY: JS, LC
CHECKED BY: SE