

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	9 Y-N-2	COOK/DUPAGE	39	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
3-4	SUMMARY OF QUANTITIES
5-11	TYPICAL SECTIONS
12	SCHEDULE OF QUANTITIES
13	ALIGNMENT, TIES AND BENCHMARKS
14	EXISTING & PROPOSED ROADWAY PLAN
15	SUE INVESTIGATION OF UNDERGROUND UTILITIES
16	EXISTING AND PROPOSED DRAINAGE PLANS
17	RIGHT OF WAY PLAN (FOR INFORMATION ONLY)
18-19	RIGHT OF WAY PLATS (FOR INFORMATION ONLY)
20	PAVEMENT MARKING AND LANDSCAPING PLANS
21	EROSION CONTROL PLAN
22	DETECTOR LOOP REPLACEMENT PLAN
23	DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING
24	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT
25	BUTT JOINT AND HMA TAPER DETAILS
25A	STEEL PLATE BEAM GUARDRAIL ADJACENT TO CURB AND GUTTER AND STABILIZATION AT TBT TY. 1 SPL
26	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
27	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW PLOW RESISTANT)
28	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
29	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)
30	PAVEMENT MARKINGS, LETTERS AND SYMBOLS FOR TRAFFIC STAGING
31	TEMPORARY INFORMATION SIGNING
32	MEDIAN NOSE DETAIL
33	DISTRICT 1 DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY RESURFACING
34	DRIVEWAY DETAILS DISTANCE BETWEEN R.O.W. AND FACE OF CURB/EDGE OF SHOULDER >= 4.5m (15')
35	DRIVEWAY DETAILS DISTANCE BETWEEN R.O.W. AND FACE OF CURB <= 4.5m (15')
36-39	CROSS SECTIONS

STATE STANDARDS

STANDARD NO.	DESCRIPTION
000001-04	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
482001-01	BITUMINOUS SHOULDER DETAILS - ADJACENT TO FLEXIBLE PAVEMENT
542606	REINFORCED CONCRETE PIPE TEE
602001	CATCH BASIN, TYPE A
602006-01	CATCH BASIN, TYPE C
604086-01	FRAME AND GRATE, TYPE 24
606001-03	CONCRETE CURB AND COMBINATION CONCRETE CURB AND GUTTER
606301-03	PC CONCRETE ISLANDS AND MEDIANS
606306-02	
630001-07	STEEL PLATE BEAM GUARDRAIL
630301-04	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
635006-02	
701301-02	LANE CLOSURE, 2L, 2W SHORT TIME OPERATIONS
701306-01	LANE CLOSURE, 2L, 2W SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS > 45 MPH
701326-02	LANE CLOSURE 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS > 45 MPH
701336-04	LANE CLOSURE 2L, 2W, WORK AREAS IN SERIES, FOR SPEEDS > 45 MPH
701601-04	URBAN LANE CLOSURE, MULTILANE 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701606-04	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701-04	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-03	LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
702001-00	TRAFFIC CONTROL DEVICES
720001	SIGN PANEL MOUNTING DETAILS
780001-01	TYPICAL PAVEMENT MARKINGS
814001-01	CONCRETE HANDHOLES
886001	DETECTOR LOOP INSTALLATION

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGE OF HINSDALE

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

10' (3 METER) TRANSITIONS SHALL BE USED TO MATCH PROPOSED CURB AND GUTTER AND MEDIAN ITEMS OF WORK TO EXISTING CURB & GUTTER AND MEDIANS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITION SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEMS OF WORK SPECIFIED.

THE RESIDENT ENGINEER SHALL CONTACT MR. DON CHIARUGI, AREA TRAFFIC FIELD ENGINEER AT (847) 741-5302 A MINIMUM OF 72 HOURS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

THE RESIDENT ENGINEER SHALL VERIFY THE LOCATIONS OF ALL EXISTING PAVEMENT MARKINGS PRIOR TO START OF CONSTRUCTION.

THE UNIT WEIGHT (CONVERSION FACTOR) QUOTED IS FOR THE ESTIMATED PLAN QUANTITIES ONLY. ACTUAL QUANTITIES TO FUFILL CONTRACT REQUIREMENTS WILL BE DETERMINED BASED ON UNIT WEIGHT OF THE APPROVED MIX DESIGN, PLAN DIMENSIONS AND DENSITY LIMITATIONS. MAXIMUM PAYMENT WILL BE COMPUTED BASED ON WEIGHT AVERAGE DENSITIES OF THE IN-PLACE MIXTURES.

ENGINEER SHALL FIELD VERIFY INVERT ELEVATIONS PRIOR TO ORDERING MATERIALS.

SAW CUTTING SHALL BE INCLUDED IN THE COST OF PAVEMENT REMOVAL, SIDEWALK REMOVAL, DRIVEWAY REMOVAL AND MEDIAN REMOVAL PAY ITEMS.

THE RESIDENT ENGINEER SHALL CONTACT MR. CORY JUCIUS, BUREAU OF TRAFFIC, AT (847) 705-4470 BEFORE FABRICATION OF "LEFT TURN AT COUNTY LINE ROAD PROHIBITED" SIGN.

THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO PLACING ANY TEMPORARY TRAFFIC CONTROL DEVICES.

PLOT DATE = 3/27/2007
 PLOT SCALE = 501/430" / IN.
 REFERENCE = #REF#

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		INDEX OF SHEETS, STATE STANDARDS, GENERAL NOTES

SCALE: VERT. DATE
 HORIZ. DRAWN BY
 CHECKED BY

R1