

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2798	3055.A-RS-1	COOK	19	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5				
40600300	AGGREGATE (PRIME COAT)	TON	20	20				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	137	137				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	450	450				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	862	862				
42001300	PROTECTIVE COAT	SQ YD	65	65				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	9960	9960				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	110	110				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	2595	2595				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	600	600				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	135	135				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	1860	1860				
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	13	13				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2673	2673				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	401	401				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3658	3658				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1735	1735				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	339	339				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	153	153				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	891	891				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	401	401				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3658	3658				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1735	1735				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	339	339				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	153	153				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	171	171				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	715	715				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	431	431				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	31	31				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				

3/28/2007

\* SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE