FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

## THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR;

REMOVAL ITEMS	HARRSION	PEOPLES	BLACKHAWK	18TH
CONTROLLER	1	1	11	1
HANDHOLE	11	2	2	1
DOUBLE HANDHOLE	2	0	0	0
HD HANDHOLE	8	1	0	1
MAST-ARM ASSEMBLY	4	5	2	22
LUMINAIRE	55	00	0	0
SIGNAL POST	10	3	4	6
SIGNAL FOUNDATION	8,	8	6	8
CONTROLLER FOUNDATION	11	1	1	11
SIGNAL HEAD	22	14	11	12
PED HEAD	8	0	2	2
PED BUTTON	8	0	2	2
SERVICE INSTALLATION	1	11	1	1

THE FOLLOWING ITEMS LISTED BELOW, ONCE REMOVED BY THE CONTRACTOR SHALL REMAIN THE PROPERTY OF THE CITY OF ROCKFORD. THE CONTRACTOR SHALL CONTACT HONG LIU, 815-987-5578 WITH THE CITY OF ROCKFORD TO ARRANGE FOR DELIVERY OR PICK-UP OF THE FOLLOWING;

- HARRISON WITH KISHWAUKEE
  1. CABINET AND CONTROLLER
  2. SIGNAL HEAD AND POSTS
  3. MAST-ARMS

- PEOPLES WITH KISHWAUKEE
  1. MAST ARMS
  2. CABINET AND EVERYTHING INSIDE
  3. SIGNAL HEADS AND POST

BLACKHAWK WITH KISHWAUKEE
1. CONTROL CABINET AND EVERYTHING INSIDE
2.SIGNAL HEADS AND POSTS

- 18TH AVE WITH KISHWAUKEE
  1. CONTROL CABINET AND EVERYTHING INSIDE
  2. SIGNAL HEADS AND POSTS

ALL OTHER ITEMS NOT LISTED IN THE ROCKFORD REQUEST SHALL BE RETAINED BY THE CONTRACTOR FOR SALVAGE.

## GENERAL NOTES

- 1. SIGNAL HEADS ON MAST ARMS SHALL BE CENTERED AND ALIGNED WITH THE APPROPRIATE LANE AT A TYPICAL SPACING OF 12'. SIGNAL HEADS POST MOUNTED SHALL BE ALIGNED WITH THE APPROPRIATE LANE.
- 2. THE MOUNTING HEIGHT FOR THE LUMINAIRES ON THE COMBINATION MASTARM ASSEMBLIES SHALL BE 35'-0" HORIZONTAL MOUNTED WITH A 12' ARM
- 4. THE RESIDENT ENGINEER SHALL DETERMINE THE LOCATION OF THE PROPOSED STOP BARS.

ILLINOIS DEPARTMENT OF TRANSPORTATION SCALE: VERT. DRAWN BY DATE CHECKED BY