

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	CARROLL	548	37
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* ROUTE 17 (US 52 / IL 64)
** (1,2)RS & (3,1)RS-1

SCHEDULE OF QUANTITIES

1	1201	+	30.00	RT	OLD 52 W
1	1202	+	10.00	RT	OLD 52 W
1	1107	+	20.00	RT	OIL VALLEY SCHOOL RD
1	1106	+	71.95	RT	OIL VALLEY SCHOOL RD
1	1104	+	19.94	RT	OIL VALLEY SCHOOL RD
1	1103	+	64.97	RT	OIL VALLEY SCHOOL RD
1	1107	+	25.00	LT	OIL VALLEY SCHOOL RD
1	1106	+	60.00	LT	OIL VALLEY SCHOOL RD
1	1104	+	80.00	LT	OIL VALLEY SCHOOL RD
1	1104	+	15.00	LT	OIL VALLEY SCHOOL RD
1	1103	+	55.00	LT	OIL VALLEY SCHOOL RD
1	58	+	70.67	LT	COMMERCIAL ST
1	59	+	84.55	LT	COMMERCIAL ST
119	TOTAL				

2
1598+90 TO 604+38

2
1 591+40 RT
1 586+40 RT
1 581+40 RT

EACH	LOCATION
12	Evenly Spaced from start to finish of Job
12	TOTAL

EACH	LOCATION
1	443 + 56.0 to 451 + 47
1	529 + 41.9 to 535 + 72.48
2	TOTAL

EQOI	LOCATION
572	444 + 65.0 - 450 + 37
375	530 + 32.0 - 534 + 7
947	TOTAL

EQOI	LOCATION
454	444 + 50.0 - 449 + 4
375	530 + 32.0 - 534 + 7
829	TOTAL

SO.FI	LOCATION
120	
120	TOTAL

EQOI	LOCATION
9	584 + 77.0
9	584 + 90.0
9	585 + 52.0
9	585 + 58.0
36	TOTAL

78200410 GUARDRAIL MARKERS, TYPE A					
EACH	LOCATION				
10	243 + 23.5 - 248 + 98.5	RT			
9	298 + 69.0 - 303 + 56.5	RT			
7	332 + 25.0 - 336 + 00	LT			
9	350 + 25.0 - 355 + 50	LT			
11	361 + 75.0 - 368 + 25	LT			
8	397 + 00 - 401 + 75	RT			
5	439 + 00 - 440 + 75	RT			
5	440 + 25.0 - 442 + 50	RT			
9	598 + 00 - 603 + 25	RT			
9	598 + 75.0 - 604 + 00	LT			
6	615 + 50.0 - 618 + 00	RT	IL 78		
6	616 + 00 - 618 + 75	LT	IL 78		
94	TOTAL				

78201000 TERMINAL MARKER - DIRECT APPLIED					
EACH	LOCATION				
1	242 + 73.4	RT			
1	249 + 48.5	RT			
1	298 + 19.0	RT			
1	304 + 6.5	RT			
1	331 + 75.0	LT			
1	336 + 50.0	LT			
1	349 + 75.0	LT			
1	356 + 00	LT			
1	361 + 25.0	LT			
1	368 + 75.0	LT			
1	396 + 50.0	RT			
1	402 + 25.0	RT			
1	438 + 50.0	RT			
1	441 + 25.0	RT			
1	439 + 75.0	RT			
1	441 + 25.0	RT			
1	597 + 50.0	RT			
1	603 + 75.0	RT			
1	598 + 25.0	LT			
1	604 + 50.0	LT			
1	615 + 00	LT	IL 78		
1	615 + 50.0	RT	IL 78		
1	618 + 65.0	LT	IL 78		
1	618 + 65.0	RT	IL 78		
24	TOTAL				

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL					
EACH	LOCATION				
66	574 + 60.00 to 584 + 90	US 52/IL 65			
31	585 + 50.00 to 590 + 20	US 52/IL 64			
18	604 + 65.00 to 608 + 00	IL 78			
26	608 + 60.00 to 612 + 90	IL 78			
141	TOTAL				

80400100 ELECTRIC SERVICE INSTALLATION					
EACH	LOCATION				
1	586 + 25.0				
1	TOTAL				

81021350 CONDUIT PUSHED, 3" DIA., PVC					
EQOI	LOCATION				
146	584 + 24.00 to 586 + 00	IL 78			
89	586 + 00 to 586 + 00	IL 78			
235	TOTAL				

81603000 UNIT DUCT, 600V, 2-1/C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA., POLYETHYLENE					
EQOI	LOCATION				
360	584 + 24.00 to 586 + 00	IL 78			
360	TOTAL				

82103900 LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT					
EACH	LOCATION				
2	584 + 24.0				
2	586 + 00				
4	TOTAL				

82500605 LIGHTING CONTROLLER PHOTOCELL RELAY					
EACH	LOCATION				
1	586 + 25.0				
1	TOTAL				

83013300 LIGHT POLE, ALUMINUM 40 FT. M.H., TRIPON MOUNT - TWIN					
EACH	LOCATION				
1	584 + 24.0				
1	586 + 00				
2	TOTAL				

83600100 LIGHT POLE FOUNDATION					
EACH	LOCATION				
1	584 + 24.0				
1	586 + 00				
2	TOTAL				

83800650 BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN					
EACH	LOCATION				
4	584 + 24.0				
4	586 + 00				
8	TOTAL				

87502460 TRAFFIC SIGNAL POST, GALVANIZED STEEL 12 FT.					
EACH	LOCATION				
1	580 + 00				
1	590 + 00				
1	604 + 00				
1	613 + 60.0				
4	TOTAL				

87800100 CONCRETE FOUNDATION, TYPE A					
EQOI	LOCATION				
3	584 + 77.0				
3	584 + 90.0				
3	585 + 52.0				
3	585 + 58.0				
12	TOTAL				

89502400 REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE					
EACH	LOCATION				
1	585 + 00				
1	TOTAL				

X0300015 CONCRETE WINGWALL REMOVAL					
EACH	LOCATION				
1	441 + 2.00	RT	US 52/IL 65		
1	TOTAL				

X0321100 GEOTEXTILE RETAINING WALL					
SO.FI	LOCATION				
320	448 + 50.69				
320	TOTAL				

X0321991 CHANNEL CLEANING					
EQOI	LOCATION				
130	470 + 31.00	RT			
130	TOTAL				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. / HORIZ.

DATE

DRAWN BY

CHECKED BY

2 REVISIED 5/31/07

SCHEDULE OF QUANTITIES

PLOT DATE = Thu Mar 22 15:27:19 2007
FILE NAME = C:\p\proj\64560\207480\cb7480\vr.dgn
PLOT SCALE = 50.00000 / IN
USER NAME = dummerba