

# SUMMARY OF QUANTITIES

CONTRACT NO. 64C60				
F.A.P. RITE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
654	109 T	CARROLL	36	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	ITEM	UNITS	TOTAL QUANTITY	80% Federal 20% STATE Y007	50% STATE 50% COUNTY** Y031-1F
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	191	191	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	76	76	
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	110	110	
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	110	110	
2 0101600	POTASSIUM FERTILIZER NUTRIENT	POUND	110	110	
20200100	EARTH EXCAVATION	CU YD	1755	1755	
20400800	FURNISHED EXCAVATION	CU YD	1136	1136	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	909	909	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2952	2952	
25000210	SEEDING, CLASS 2A	ACRE	0.4	0.4	
25000310	SEEDING, CLASS 4	ACRE	0.21	0.21	
25000750	MOWING	ACRE	0.2	0.2	
25100115	MULCH, METHOD 2	ACRE	0.61	0.61	
25100630	EROSION CONTROL BLANKET	SQ YD	158	158	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	160	160	
28000300	TEMPORARY DITCH CHECKS	EACH	28	28	
28000400	PERIMETER EROSION BARRIER	FOOT	231	231	
28000500	INLET AND PIPE PROTECTION	EACH	2	2	
31100935	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	SQ YD	909	909	
40600990	TEMPORARY RAMP	SQ YD	54	54	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	186	186	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	214	214	
50100200	REMOVAL OF EXISTING STRUCTURES	L SUM	1	1	
50800105	REINFORCEMENT BARS	POUND	61	61	
51500100	NAME PLATES	EACH	1	1	

■ NON-PARTICIPATING 100% STATE

PLOT DATE = Fri Mar 16 11:05:35 2007  
 PLOT SCALE = 5000000  
 USER NAME = g01fj