

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
654	109 T	CARROLL	36	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

40600990 TEMPORARY RAMP

SQ.YD	LOCATION	REMARKS
27	<u>Peace & Quiet Road</u> Sta. 18+00.0	
27	Sta. 19+87.0	
54	TOTAL	

54002020 EXPANSION BOLTS 3/4 INCH

EACH	LOCATION	REMARKS
6	<u>IL 73</u> LT. Sta. 326+94	Used at the concrete collar location

40800050 INCIDENTAL HOT-MIX ASPHALT SURFACING

TON	LOCATION	REMARKS
186	<u>Peace & Quiet Rd</u> L & R Sta. 18+00.0 - 19+87.0	ARE IS 947 SQ.YDS
• SHOULDERS ARE INCLUDED		

54010203 CONCRETE BOX CULVERT 2'x3'

FOOT	LOCATION	REMARKS
27	<u>IL 73</u> LT. Sta. 327+20	

48101200 AGGREGATE SHOULDERS TYPE B

TON	LOCATION	REMARKS
9	<u>IL 73</u> LT. Sta. 324+20 - 324+54.0	
187	LT. Sta. 326+45.0 - 333+50.0	
17	<u>Peace & Quiet Road</u> L & R Sta. 18+00.0 - 18+65.0	
214	TOTAL	

54213471 END SECTION 36"

EACH	LOCATION	REMARKS
1	<u>Peace & Quiet Road</u> LT. Sta. 19+17	

50100200 REMOVAL OF EXISTING STRUCTURES

L. SUM	LOCATION	REMARKS
1	<u>Peace & Quiet Road</u> LT. Sta. 18+99	Used at the concrete collar location

54201081 PIPE CULVERTS, CLASS D, TYPE 2, 36"

FOOT	LOCATION	REMARKS
94	<u>Peace & Quiet Road</u> Sta. 18+99	

50800105 REINFORCEMENT BARS

POUND	LOCATION	REMARKS
61	<u>IL 73</u> LT. Sta. 326+94	Used at the concrete collar location

54248510 CONCRETE COLLAR

CU.YD	LOCATION	OFFSET (ft)	REMARKS
1	<u>IL 73</u> LT. Sta. 326+94	31.52	2' X 3' Box Culvert Extension

51500100 NAME PLATES

EACH	LOCATION	REMARKS
1	<u>IL 73</u> LT. Sta. 327+20	AT THE BOX CULVERT EXTENSION

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)

EACH	LOCATION	REMARKS
1	<u>IL 73</u> RT Sta. 326+34 - 326+84	
1	RT Sta. 328+34 - 328+84	50' Long
2	TOTAL	50' Long

PLOT DATE = Sat Apr 14 09:27:52 2007
 FILE NAME = c:\pcc\pcc\pcc\210306\410306.dgn
 PLOT SCALE = 56.0000 / IN.
 USER NAME = geffj