

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
654	109 T	CARROLL	36	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION	REMARKS
	<u>IL 73</u>	
38	RT Sta. 326+46 - 326+84	
38	RT Sta. 328+34 - 328+72	
<u>189</u>	LT. Sta. 326+04 - 327+93	
265	TOTAL	

63500105 DELINEATORS

EACH	LOCATION	REMARKS
	<u>IL 73</u>	
1	LT. Sta. 326+34	AT BEGINNING OF TERMINALS
1	LT. Sta. 328+84	AT END OF TERMINALS
1	LT. Sta. 326+77	AT THE DROP LOCATION
	<u>Peace & Outlet Rd</u>	
1	RT Sta. 18+87	AT DROP BOX LOCATION
<u>1</u>	LT. Sta. 19+17	AT END SECTION LOCATION
5	TOTAL	

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION	OFFSET (ft)	REMARKS
	<u>IL 73</u>		
1	LT. Sta. 328+00	70	
1	LT. Sta. 330+00	60	
1	LT. Sta. 331+00	51	
	<u>Peace & Outlet Rd</u>		
1	RT. Sta. 17+00	36	
1	LT. Sta. 17+00	30	
1	RT. Sta. 18+00	75	
1	LT. Sta. 18+00	60	
1	LT. Sta. 19+00	60	
<u>1</u>	RT. Sta. 19+47	75	
9	TOTAL		

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION	REMARKS
	<u>IL 73</u>	
2	ENTIRE JOB	USE ONE AT EACH SIDE OF THE CULVERT ALONG IL 73.

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION (2 APPLICATIONS)	REMARKS
	<u>IL 73</u>	
2520	L & R. Sta. 324+20 - 330+50	White Edge line
374	RT. Sta. 18+00 - 19+87	White Edge line
374	LT. Sta. 18+00 - 19+87	White Edge line
<u>748</u>	Sta. 18+00 - 19+87	Double Yellow
4016	TOTAL	

78001180 PAINT PAVEMENT MARKING - LINE 24"

FOOT	LOCATION (2 APPLICATIONS)	REMARKS
70	<u>Peace & Outlet Rd</u> Sta. 19+67	Stop Bar

78201000 TERMINAL MARKER-DIRECT APPLIED

EACH	LOCATION	REMARKS
	<u>IL 73</u>	
1	RT Sta. 326+34	AT BEGINNING OF TERMINALS
1	RT Sta. 328+84	AT END OF TERMINALS
<u>2</u>	TOTAL	

X0323660 DROP BOX NO. 1

EACH	LOCATION	OFFSET (ft)	REMARKS
	<u>IL 73</u>		
1	LT. Sta. 326+77	53.8'	

X0323661 DROP BOX NO. 2

EACH	LOCATION	OFFSET (ft)	REMARKS
	<u>Peace & Outlet Rd</u>		
1	LT. Sta. 18+87	39.50	

X0325519 DRAIN FOR AGGREGATE BASE COURSE

SO. YD.	LOCATION	OFFSET (ft)	REMARKS
	<u>Peace & Outlet Rd</u>		
1	LT. Sta. 19+00		

XX005938 SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)

EACH	LOCATION	REMARKS
	<u>NOTE: OUT SIDE PROJECT LIMITS.</u>	
1	W. Sabin Church Road" Just west of the intersection'	call Kurt Glazier (815-284-5478) from 100' prior to the installation of these flashers for location approval
1	on the current stop sign on W. Sabin Church Road intersection	
1	W. Bolton Road-North leg.	
<u>1</u>	W. Bolton Road-South leg.	
4	TOTAL	

Z0020900 ESTABLISHING AND REFERENCING LAND SECTION MARKERS

EACH	LOCATION	OFFSET (ft)	REMARKS
	<u>IL 73</u>		
1	LT. Sta. 326+03	20.62	NW. CORNER

PLOT DATE = Sat Apr 14 09:27:53 2007
 FILE NAME = s:\projects\64c60\101110\101110.dgn
 PLOT SCALE = 3/8" = 1' IN.
 USER NAME = gcfj