CONTRACT NO. 66602

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
301	*	**	18	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*113RS-3 & 114RS-2 **GRUNDY & WILL

SUMMARY OF QUANTITIES

80% FEDERAL 20% STATE

CONSTRUCTION CODE TYPE: I000-2A

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	GRUNDY STA. 8+27 TO STA. 160+34	WILL STA. 160+34 TO STA. 191+22
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	21		21
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3979	3130	849
40600300	AGGREGATE (PRIME COAT)	TON	99	78.4	20.6
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	14	10.8	3.2
40600525	LEVELING BINDER (HAND METHOD), N50	TON	23	17.8	5.2
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	429		429
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	309		309
4060985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	32		32
40600990	TEMPORARY RAMP	SQ YD	587	555.9	31.1
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N70	TON	3798	2933	865
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	388	352	36
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	39251	39115	136
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	216		216
△1 44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	25		25
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	130		130
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	4	4	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	1	1
67100100	MOBILIZATION	L SUM	1	0.7	0.3
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1
△1 70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1		1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4028	3312	716
70300610	TEMPORARY PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	78	78	
70300625	TEMPORARY PAINT PAVEMENT MARKING - LINE 4"	FOOT	4663	4663	
70300635	TEMPORARY PAINT PAVEMENT MARKING - LINE 6"	FOOT	2700	2700	
70300640	TEMPORARY PAINT PAVEMENT MARKING - LINE 8"	FOOT	373	373	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	671	552	119
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	257.9	257.9	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11409	4663	6746
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3420	2690	730
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	373	373	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	291	279	12
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	81	81	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	244	197	47
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	237	190	47
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

△1 REVISED 5/29/07
* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

DATE-TIME
c:\projects\ed06305\summary.dgn