

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
35RS-5,36RS-8	TAZEWELL	90	41	
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*6717 (BUS 24) & 6713 (IL 8)				

RESURFACING - IL 8

	AREA	HMA SURF REMOVAL BT JT	HMA SURF REMOVAL 1-1/2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA SURFACE REMOVAL 1/2 INCHES	LEVELING BINDER MM, N50	POLY HMA SURF CSE. MIX D, N70
	SQ FT	SQ YD	SQ YD	TON	TON	SQ YD	TON	TON
MAINLINE								
203+00 - 222+00	74600	75.6		3.85	22.2	7400	310.8	621.6
222+00 - 228+00	22799.7			1.32	7.6	2533.3	106.4	212.8
228+00 - 232+00	16000.2			0.92	5.3	1777.8	74.7	149.3
232+00 - 240+00	26399.7			1.53	8.8	2933.3	123.2	246.4
240+00 - 258+65	50231.7			2.86	16.7	5498	234.4	468.8
MEADOWVIEW LN. (NORTH)	1500	166.6		0.06	0.3			14.0
MEADOWVIEW LN. (SOUTH)	1500	166.6		0.06	0.3			14.0
SCHOOL ST. (NORTH)	2870.1	206.7		0.17	1.0	112.2	4.7	26.8
SCHOOL ST. (SOUTH)	2809.8	190		0.16	0.9	122.2	5.1	26.2
GRANT ST.	540.0	60		0.02	0.1			5.0
VOHLAND ST.	860.0	95.6		0.04	0.2			8.0
MCGINLEY ST.	460.0	51.1		0.02	0.1			4.3
WAGNER ST.	460.0	51.1		0.02	0.1			4.3
ERNEST ST.	560.0	62.2		0.02	0.1			5.2
258+65 - 258+95	750.0			0.03	0.2			7.0
258+95 - 266+19.70	20782.5		2309.2	0.92	4.6			194.0
EAST BOUND								
266+19.70 - 321+98	132925.8		14769.5	5.91	29.5			1240.6
321+98 - 322+28	744.5	82.7		0.03	0.2			6.9
TURNLANES								
319+64.44 - 322+28	3097.8	44.1	261.5	0.12	0.5			25.7
312+25 - 317+50	5405.7		600.6	0.24	1.2			50.5
267+83.11 - 272+93.58	4598.7		511.0	0.20	1.0			42.9
312+15 - 318+39.02	5792.1		643.6	0.26	1.3			54.1
280+00 - 284+26.88	5730.9		636.8	0.25	1.3			53.5
298+99.29 - 304+29.66	4929.1		547.7	0.22	1.1			46.0
292+02.70 - 297+00	4205.0		467.2	0.19	0.9			39.2
WEST BOUND								
266+19.70 - 321+98	131605.3		14622.8	5.85	29.2			1228.3
321+98 - 322+28	720.7	80.1		0.03	0.2			6.7
TURNLANES								
271+19.57 - 276+65.27	4739.0		526.6	0.21	1.1			44.2
283+00 - 290+57.16	7612.2		845.8	0.34	1.7			71.0
296+11.24 - 300+88.13	4034.5		448.3	0.18	0.9			37.7
316+60 - 320+40	4092.9		454.8	0.18	0.9			38.2
302+60 - 307+88.69	4466.8		496.3	0.20	1.0			41.7
316+01.69 - 322+28	6290.1	5.1	693.8	0.28	1.4			58.7
CROSSOVERS								
272+52.16	806.7		89.6	0.04	0.2			7.5
279+00	2117.2		235.2	0.09	0.5			19.8
284+77.81	1036.1		115.1	0.05	0.2			9.7
296+39.73	1153.0		128.1	0.05	0.3			10.8
303+60	588.4		65.4	0.03	0.1			5.5
TOTALS		1413	39469	27	142	20377	860	5147

STRIP REFLECTIVE CRACK CONTROL TREATMENT	
E. B. IL 8	FOOT
STA. 215+15 - 227+35	1220

AGGREGATE SUFACE COURSE, TYPE B	
IL 8	TON
STA. 204+50 - 257+50	21.0
TOTAL	21

MANHOLES TO BE ADJUSTED	
LOCATION	EACH
46 FT RT STA 227+60	1
TOTAL	1

EROSION CONTROL CURB	
LOCATION	FOOT
IL 8 EB	
STA. 281+00-285+00	400
STA. 292+50-294+00	150
TOTALS	550

EROSION CONTROL CURB REMOVAL	
LOCATION	FOOT
IL 8 EB	
STA. 281+00-285+00	400
STA. 292+50-294+00	150
TOTALS	550

NEW SHEET 61107

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: VERT. DATE
HORIZ. DATE

DRAWN BY
CHECKED BY

PLOT DATE : 5/21/2007
FILE NAME : C:\Documents and Settings\user\Worktop\constr\plan\dgn
PLOT FILE : 30413724 / PL
USER NAME : bruce